



### Agenda

- Project Understanding and Approach
- Firm Introduction
- Relevant Projects
- Team Organizational Chart
- CPM Project Milestone Schedule
- Staffing Chart
- Summary Estimate
- Detailed Trade Take-Off

- Value Engineering Proposal
- Construction Site Logistics Plan
- Construction Site Safety Plan
- Quality Assurance/Quality Control Plan
- Constructability Review
- Sustainable Construction Plan
- Construction Technology Initiative



# Project Understanding and Approach


#### Project Details:

- 86,040 square feet
- 6-story building
- Exterior facade and structural support to remain
- Installation of two (2) elevators and fire stair in the center of the building
- Full removal and replacement of:
  - Electrical
  - Plumbing
  - Fire Protection
  - HVAC

#### • Project Approach:

- Four Phases
  - Demolition
  - Structural
  - MEP
  - Interior Fit-Out







#### **BUILDWORKS CONSTRUCTION**

- Founded by Timothy Build and John Works in 1980
- Firm Headquarters: 767 5<sup>th</sup> Avenue, New York, NY 10153
- 150 Full Time Employees
- Annual Revenue: \$225 Million
- Average Project Cost: \$9 Million
- Values Integrity of work, Safety of employees, and Collaboration of teams

### Firm Introduction







### **Golten Marine Building**

**Client:** LIVWRK

Location: 160 Van Brunt Street, Brooklyn, NY 11231

**Size:** 98,650 SF

Cost: \$5.5 Million

**Completion:** 2016

**Architect:** John Saracco Architects

• Interior fit-out


HVAC Mechanical system

• Vertical Transportation

Lobby Renovation

### **Relevant Projects**









### Relevant Projects

#### **Asana**

Client: Asana

Location: 3 World Trade Center, 36th Floor,

New York, NY 10007

**Size:** 18,000 SF

Cost: \$1.2 Million

**Completion:** 2019

A/E Team: Murdock Solon Architects/ 2L Consulting

Engineering

Office Fit-Out

Pantry space

Private Restrooms

• Redistribution of perimeter heating of the building



### Relevant Projects

#### The Warehouse

**Client:** Elijah Equities/ Newmark Grubb Knight Frank

**Location:** 520 W 20th St, New York, NY 10011

**Size:** 115,855 SF

Cost: \$15.9 Million

**Completion:** 2020


**Architect:** Morris Adjmi Architects

• Community Redevelopment


• Interior Fit-Out

Expansion above building

Redesign of vertical cores









### Relevant Projects

#### Luxottica

**Client:** Luxottica

**Location:** 12 Harbor Park Dr, Port Washington, NY 11050

**Size:** 30,000 SF

Cost: \$2.5 Million

**Completion:** 2016


**Architect:** Mojo Stumer Architects

• Warehouse converted to Office Space

• Two story Atrium with skylight

Installation of green living wall







### **CPM Milestone Schedule**

June 1, 2021 to April 11, 2022

MILESTONE	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER	JANUARY	FEBRUARY	MARCH	APRIL
Procurement	Х	Х									
Demolition/Excavation		X	X	X							
Structural				X	X						
Fire Stair					X	X					
Elevator Installation					X	X	X				
MEP Rough-In							X	X	Х		
Interior Finishes								X	Х	X	
Close-Out									X	X	X



### Three-Week Look Ahead

								7/19	9/20	21 - 8	8/6/2	2021							
ACTIVITY	M	Т	W	TH	F	S	S	M	T	W	TH	F	S	S	M	T	W	TH	F
A/E Review for Final Submittals	Х																		
Site Mobilization	X	X																	
Site Clearance		X																	
Site Fence Installation		X																	
Interior Demo 6th Floor			X	X	X			X											
6th Floor Concrete Slab Demo											X	X							
Interior Demo 5th Floor								X	X	X	X								
5th Floor Concrete Slab Demo																X	X		
Interior Demo 4th Floor											X	X			Х	X			
4th Floor Concrete Slab Demo																			X
Interior Demo 3rd Floor																X	X	X	X



# **Staffing Chart**

		<b>AVERAGE HOURS</b>	TOTAL HOURS	PERCENT OF
NAME	ROLE	PER MONH	AVAILABLE	TIME
<b>Anthony Ferrara</b>	PRESIDENT & CEO	14.55	160	9%
Michael Hall	PROJECT EXECUTIVE	36.36	160	23%
Chloe Decker	PROJECT MANAGER	76.36	160	48%
Vince Masuka	SENIOR ESTIMATOR	33.64	160	21%
Joe Goldberg	PROJECT SUPERINTENDENT	160.00	160	100%
Rami Malek	ASSISTANT SUPERINTENDENT	160.00	160	100%
Laura Linney	PROJECT ENGINEER	160.00	160	100%
James Doakes	SITE SAFETY SUPERVISOR	160.00	160	100%



### SUMMARY BID ESTIMATE

PROJECT: Urban Yard

LOCATION: 40-09 21st Street, LIC, NY, 11101

FIRM: BuildWorks Construction

DATE: April 26, 2021



		86040 SF					
Divisions (Tr	ades)		Cost (\$)	Cost per SF (\$)	Percentage of Cost (%)		
			005 000 00	<b>A</b> 0.70	0.400/		
Division 01	General Requirements	\$	325,000.00	\$ 3.78	3.42%		
Division 02	Existing Conditions	\$	446,773.00	\$ 5.19	4.70%		
Division 03	Concrete	\$	859,350.00	\$ 9.99	9.04%		
Division 04	Masonry	\$	242,875.00	\$ 2.82	2.56%		
Division 05	Metals	\$	274,235.00	\$ 3.19	2.89%		
Division 06	Wood, Plastics, and Composites	\$	328,750.00	\$ 3.82	3.46%		
Division 07	Thermal and Moisture Protection	\$	212,350.00	\$ 2.47	2.23%		
Division 08	Openings	\$	213,780.00	\$ 2.48	2.25%		
Division 09	Finishes	\$	639,764.00	\$ 7.44	6.73%		
Division 10	Specialties	\$	335,475.00	\$ 3.90	3.53%		
Division 11	Equipment	\$	551,870.00	\$ 6.41	5.81%		
Division 12	Furnishings	\$	127,750.00	\$ 1.48	1.34%		
Division 13	Special Construction	\$	210,872.00	\$ 2.45	2.22%		
Division 14	Conveying Equipment	\$	609,435.00	\$ 7.08	6.41%		
Division 21	Fire Suppression	\$	683,560.00	\$ 7.94	7.19%		
Division 22	Plumbing	\$	754,870.00	\$ 8.77	7.94%		
Division 23	Heating, Ventilating, and Air-Conditioning	\$	849,940.00	\$ 9.88	8.94%		
Division 26	Electrical	\$	691,584.00	\$ 8.04	7.28%		
Division 27	Communications	\$	103,972.00	\$ 1.21	1.09%		
Division 28	Electronic Safety and Security	\$	242,875.00	\$ 2.82	2.56%		
Division 31	Earthwork	\$	285,390.00	\$ 3.32	3.00%		
Division 32	Exterior Improvements	\$	150,745.00	\$ 1.75	1.59%		
Division 33	Utilities	\$	360,985.00	\$ 4.20	3.80%		
	TRADE SUBTOTAL		\$9,502,200.00	\$110.44	100.00%		
	Building Permit Fees	\$	190,044.00	\$ 2.21	2.00%		
	Payment & Performance Bonds	\$	-	\$ -	0.00%		
	General Conditions - Reimbursables	\$	190,044.00	\$ 2.21	2.00%		
	CM Staff	\$	760,176.00	\$ 8.84	8.00%		
	Overhead & Profit	\$	950,220.00	\$ 11.04	10.00%		
	Insurance	\$	380,088.00	\$ 4.42	4.00%		
	FEES SUBTOTAL	\$	2,470,572.00	\$ 28.71			
	TOTAL		\$11,972,772.00	\$139.15			



### **Detailed HVAC Estimate**

PROJECT: Urban Yard	
DETAILED HVAC LOCATION: [40-09 21st Street, LIC, NY, 1	1101)
TAKE-OFF FIRM: BuildWorks Construction	
DATE: April 26, 2021	BuildWorks Construction
	86040 SF
Line Item Division 23 HVAC Unit Cost (\$)	Quantity Total Cost (\$)
Cellar	
1 EWH-1 \$ 200.00	3 \$ 600.00
Ground Floor	OTAL - CELLAR: \$ 600.00
2 EWH-1 \$ 200.00	2 \$ 400.00
3 EH-1 \$ 200.00	9 \$ 1.800.00
4 EH-2 \$ 250.00	15 \$ 3,750.00
5 ER-1 \$ 40.00	4 \$ 160.00
6 AC UNITS \$ 750.00	13 \$ 9,750.00
	1074 FT \$ 37,555.00
	ROUND FLOOR: \$ 53,415.00
2nd Floor	5 4 000 00
8 EH-1 \$ 200.00 9 EH-2 \$ 250.00	5 \$ 1,000.00 20 \$ 5.000.00
9 EH-2 \$ 250.00 10 ER-1 \$ 40.00	20 \$ 5,000.00 4 \$ 160.00
11 AC UNITS \$ 750.00	12 \$ 9.000.00
	1074 FT \$ 37,590.00
SUBTOT/	AL - 2ND FLOOR: \$ 52,750.00
3rd Floor	
13 EH-1 \$ 200.00	5 \$ 1,000.00
14 EH-2 \$ 250.00	20 \$ 5,000.00
15 ER-1 \$ 40.00	4 \$ 160.00
16 AC UNITS \$ 750.00 17 REFRIGERANT PIPING \$ 35.00	12 \$ 9,000.00 1074 FT \$ 37.590.00
	1074 FT \$ 37,590.00 AL - 3RD FLOOR: \$ 52.750.00
4th Floor	AL - 3RD FLOOR: \$ 52,750.00
18 EH-1 \$ 200.00	5 \$ 1,000.00
19 EH-2 \$ 250.00	20 \$ 5,000.00
20 ER-1 \$ 40.00	4 \$ 160.00
21 AC UNITS \$ 750.00	12 \$ 9,000.00
	1074 FT \$ 37,590.00
	AL - 4TH FLOOR: \$ 52,750.00
5th Floor	5 400000
23 EH-1 \$ 200.00 24 EH-2 \$ 250.00	5 \$ 1,000.00 20 \$ 5.000.00
24 EH-2 \$ 250.00 25 ER-1 \$ 40.00	4 \$ 5,000.00
26 AC UNITS \$ 750.00	12 \$ 9,000.00
	1074 FT \$ 37.590.00
	AL - 5TH FLOOR: \$ 52.750.00
6th Floor	
28 EH-1 \$ 200.00	5 \$ 1,000.00
29 EH-2 \$ 250.00	20 \$ 5,000.00
30 ER-1 \$ 40.00	4 \$ 160.00
31 AC UNITS \$ 750.00	12 \$ 9,000.00
	1074 FT \$ 37,590.00
	AL - 6TH FLOOR: \$ 52,750.00
Roof	1 \$ 200.00
36 ACCU \$ 12.000.00	12 \$ 144,000,00
7.000	BTOTAL - ROOF: \$ 144,200.00
301	177,200.00
	SUBTOTAL \$461,965.00
	LABOR COSTS \$ 387,975.00
	TOTAL \$849,940.00



### **Detailed HVAC Estimate**

		PROJECT:	Urban Y	/ard	at	
	<b>DETAILED HVAC</b>	LOCATION:	40-09 21st Street, I	LIC, NY, 11101)		
		FIRM:	BuildWada Co		Ш	
	TAKE-OFF	FIRM:	BuildWorks Co			Compton of the second
		DATE:	April 26,	2021 Build Wor	KS (	Construction
				86040 SF		
Line Item	Division 23 HVAC		Unit Cost (\$)	Quantity		Total Cost (\$)
	Cellar					
1	EWH-1	\$	200.00	3	\$	600.00
				SUBTOTAL - CELLAR:	\$	600.00
	Ground Floor					
2	EWH-1	\$	200.00	2	\$	400.00
3	EH-1	\$	200.00	9	\$	1,800.00
4	EH-2	\$	250.00	15	\$	3,750.00
5	ER-1	\$	40.00	4	\$	160.00
6	AC UNITS	\$	750.00	13	\$	9,750.00
7	REFRIGERANT PIPING	\$	35.00	1074 FT	\$	37,555.00
			SUB	TOTAL - GROUND FLOOR:	\$	53,415.00
	2nd Floor					
8	EH-1	\$	200.00	5	\$	1,000.00
9	EH-2	\$	250.00	20	\$	5,000.00
10	ER-1	\$	40.00	4	\$	160.00
11	AC UNITS	\$	750.00	12	\$	9,000.00
12	REFRIGERANT PIPING	\$	35.00	1074 FT	\$	37,590.00
				SUBTOTAL - 2ND FLOOR:	\$	52,750.00
	3rd Floor					
13	EH-1	\$	200.00	5	\$	1,000.00
14	EH-2	\$	250.00	20	\$	5,000.00
15	ER-1	\$	40.00	4	\$	160.00
16	AC UNITS	\$	750.00	12	\$	9,000.00
17	REFRIGERANT PIPING	\$	35.00	1074 FT	\$	37,590.00
				SUBTOTAL - 3RD FLOOR:	\$	52,750.00


			PROJECT:	Urban Y	ard		
ll						пП	
ll		DETAILED HVAC	LOCATION:	40-09 21st Street, L	.IC, NY, 11101		<b>.</b>
l		TAKE-OFF	FIRM:	BuildWorks Co	nstruction		- 1
			DATE:	April 26, 2	2021 BuildWor	ks (	Construction
اا			JA. L.	7 sprii 20, 1			
ا	Line Item	Division 23 HVAC		Unit Cost (\$)	86040 SF Quantity		Total Cost (\$)
اا	Line item	4th Floor		Offic Cost (\$)	Quantity		Total Cost (3)
1	40	***************************************	•	000.00			4 000 00
1	18	EH-1	\$	200.00	5	\$	1,000.00
1	19	EH-2	\$	250.00	20	\$	5,000.00
۱	20	ER-1	\$	40.00	4	\$	160.00
۱	21	AC UNITS	\$	750.00	12	\$	9,000.00
l	22	REFRIGERANT PIPING	\$	35.00	1074 FT	\$	37,590.00
ı					SUBTOTAL - 4TH FLOOR:	\$	52,750.00
ł		5th Floor					
l	23	EH-1	\$	200.00	5	\$	1,000.00
ı	24	EH-2	\$	250.00	20	\$	5,000.00
1	25	ER-1	\$	40.00	4	\$	160.00
1	26	AC UNITS	\$	750.00	12	\$	9,000.00
l	27	REFRIGERANT PIPING	\$	35.00	1074 FT	\$	37,590.00
l					SUBTOTAL - 5TH FLOOR:	\$	52,750.00
1		6th Floor					
1	28	EH-1	\$	200.00	5	\$	1,000.00
	29	EH-2	\$	250.00	20	\$	5,000.00
l	30	ER-1	\$	40.00	4	\$	160.00
1	31	AC UNITS	\$	750.00	12	\$	9,000.00
	32	REFRIGERANT PIPING	\$	35.00	1074 FT	\$	37,590.00
					SUBTOTAL - 6TH FLOOR:	\$	52,750.00
1		Roof					
1	33	EWH-1	\$	200.00	1	\$	200.00
1	36	ACCU	\$	12,000.00	12	\$	144,000.00
ĺ					SUBTOTAL - ROOF:	\$	144,200.00
							,
					SUBTOTAL		\$461,965.00
					LABOR COSTS	S	387,975.00
					TOTAL		\$849,940.00



Value Engineering Proposal







**01** LOBBY RENDERING SCALE: N.T.S.



# Value Engineering Proposal



**02** TYPICAL HALLWAY SECTION RENDERING SCALE: N.T.S.

#32 #32 #32 | T14 | #32 | T15 | #32 | T14 | #32 | T15 | T15 | #32 | T15 | T15



## Value Engineering Proposal



#### **SPECIFIED LT2 LIGHTING FIXTURE**

• Manufacturer: Industrial Light Electric

• Ceiling Canopy: 5" Diameter

• Rated: 60W, 120V

• Bulb Base/Shape: Medium E26/G25

	SPECIFIED			ALTERNATIVE				
Quantity:		135		135				
Unit Price:	\$	55.00	\$	20.99				
Total:	\$	7,425.00	\$	2,833.65				
Savings:	\$	-	\$	4,591.35				
Percentage:				62%				

#### **VE ALTERNATIVE LT2 LIGHTING FIXTURE**

• Manufacturer: Nuvo

• Ceiling Canopy: 5" Diameter

Rated: 60W, 120V

• Bulb Base/Shape: Medium E26/G25





## **Site Logistics**




### **LEGEND**

→ Flow of Traffic




### **Site Logistics**





### Flow of Work





### Phases of Project

Top Floor Down

#### • Phase 1

- Demolition from top level down to cellar
- Floor slab demo delayed by 2 floors

#### Phase 2


- Construction from cellar level up
- Exterior Material storage transferred to ground level as needed

#### • Phase 3

• MEP Installation from center, out

#### Phase 4

Interior Fit-out from center, out





### Construction Site Safety Plan

- People are our #1 Assets
- EMR Rating of 0.8
- Accident Prevention Plan is constantly updated to adjust with the Project Conditions






### Minimum Requirements

- Required, at minimum, the following requirements:
- Completion of OSHA-30 Certification
- Pre-employment drug test
- Substance abuse background check
- Completion of the Site Safety Orientation, signed off by the Site Safety Supervisor


Failure to provide the stated requirements may result in the immediate removal from the jobsite.







## **FDNY**




Enterprise Rent A-Car

Grant Supplies

D Photo Studio NY



### Fire Extinguisher Location




Eyewash/Handwash Station

Fire Extinguisher



### **Emergency Room**



3019 Crescent Street, LIC, NY 11102 (718) 932-1000


James Doakes **Site Safety Supervisor**(917) 786-5600

Michael Hall **Project Executive**(917) 786-2400




#### Net for Falling Debris

- Guard Rails for Fall Protection
- Scheduled lag for floor slab demolition




### Floor Slab Demolition






### COVID-19

- Temperature Screening
- Handwash Stations
- N95 Masks Supplied
- Social Distancing








### QA/QC Plan


- Quality Assurance Process
  - Checks the quality plan and quality control process to confirm that quality standards are implemented on the project site.
- Quality Control Process
  - Confirms the project outcome meets the client's standards
- Key Factors of a Successful Project:
  - Completion of the project on schedule as per the contract document
  - Quality of the project as per the company's standards.





## **Quality Assurance**

- Submittals
  - Procore
- Samples/ Mockups
  - Finishes
- Pre-Installation Meetings
  - MEP trades
  - Sequence of work
- Certifications/Warranties





### **Quality Control**

- Delivery Inspections
  - Material
  - Equipment
- Tests/Inspections
  - Elevator Installation
  - Fire Stair
- Commissioning









# REQUEST FOR INFORMATION FORM RFI # 001 DATE 4/26/2021 DATE NEEDED BY 5/10/2021 PROJECT NAME Urban Yards PROJECT # 210026

#### **RFI** Description

The design of the typical (TYP.) bathrooms for the 2nd through 6th floor shows a plan for a total of four water closets and a urinal. There is a gender-neutral ADA compliant bathroom separate from the Men's and Women's bathrooms. According to the drawings, the location of the G-2 column blocks the path for the required pipes to reach the sink of the ADA compliant bathroom and the urinal, as shown in the marked up drawing (left) below. Additionally, multiple drawings in the Plumbing Set show that this area of the building is mislabeled where the labelling of the items within the bathrooms are far from the actual item it is referencing, as shown on the drawing (right) below. Please identify how the marked sink and urinal are to be connected without interference by the G-2 column.





ATTACHMENTS: P-302 Plumbing 2nd and 3rd Floor Plan, P-303 Plumbing 4th and 5th Floor Plan


SUBMITTED BY: Laura Linney, Project Engineer
BuildWorks Construction


#### **ATTACHMENTS**



#### **RFI** Description

The design of the typical (TYP.) bathrooms for the 2nd through 6th floor shows a plan for a total of four water closets and a urinal. There is a gender-neutral ADA compliant bathroom separate from the Men's and Women's bathrooms. According to the drawings, the location of the G-2 column blocks the path for the required pipes to reach the sink of the ADA compliant bathroom and the urinal, as shown in the marked up drawing (left) below. Additionally, multiple drawings in the Plumbing Set show that this area of the building is mislabeled where the labelling of the items within the bathrooms are far from the actual item it is referencing, as shown on the drawing (right) below. Please identify how the marked sink and urinal are to be connected without interference by the G-2 column.








<u>Design Conflicts for Bathrooms –</u> 2<sup>nd</sup> to 6<sup>th</sup> Floor

- G-2 Column in path of connection pipes
  - ADA bathroom sink
  - Urinal
- Mislabeled locations of bathroom components

### **Referenced Drawing:**


- P-302 Plumbing 2<sup>nd</sup> and 3<sup>rd</sup> Floor Plan
- P-303 Plumbing 4<sup>th</sup> and 5<sup>th</sup> Floor Plan






### **Possible Solutions**


- Increase wall width by 4"
  - Allows space for pipes to reach the sink and urinal
  - Allows clearance for the G-2 column
- Use alternate design plan
  - Shown in Interior Fit-Out drawings
  - All components requiring a connection is against one wall
  - Vertical stacks are better positioned for this design














**PROPOSED** 










I-03

I-03


I-14

**I-20** 













**PROPOSED** 









A-102

I-03

I-14

**I-20** 






**01** PUBLIC RESTROOM SECTION RENDERING SCALE: N.T.S.

I-13 Public Restroom Rendering & Schedule





02 ELEVATION SCALE: 3/8" = 1'-0"


I-14 Public Restroom Elevations




### Sustainable Construction Plan

#### United Nations Environmental Program

- 35% of global energy use
- 38% of carbon dioxide emissions









### Sustainable Construction Plan

#### **Improve Air Quality**

- Green Dust
- Air Filters
- Dust Barrier System

### **Reduce Energy Emission**

• Use electric vehicle alternatives when possible









### Sustainable Construction Plan

#### **Construction Waste Management Plan**

#### **Waste Management Plan**

- Meet with subcontractors to discuss the proper disposal of materials
- Monitor to ensure correct disposal

#### **Commissioning**

- Verify equipment and system performance
- Establish protocols for scheduled commissioning activities
- Ensure operating personnel are adequately trained


	Waste Description	Re-Use	Onsite	Off-site	Recycle	On Site	Off-Site	Dispose	On Site	Off-Site
启	Bricks		Yes				Yes			Yes
Inert	Add Text Here			Yes		Yes				Yes
	Add Text Here			Yes		Yes				Yes
۵	Plastic Pipes		Yes				Yes		Yes	
Non- Hazard	Plastic Wirings			Yes		Yes			Yes	
	Add Text Here			Yes		Yes			Yes	
Δ	Bio-Chemical			Yes		Yes				Yes
Hazard	Lead		Yes			Yes				Yes
	Add Text Here		Yes			Yes				





# **Construction Technology**

#### **The Construction Management Platform**



MANAGE

WORKFLOWS

**CREATE A SINGLE** 

SOURCE OF TRUTH

PROMOTE

SAFETY

(1) User activity generated over 3,000 terabytes of data as of December 31, 2019.

(2) Total volume and projects data generated since January 1, 2014, as of December 31, 2019.

STREAMLINE

COMMUNICATION

(3) Represents user activity during Fiscal 2019.

DIGITIZE

**DOCUMENTS** 




#### **Procore**

- Submittals
- RFI's
- Construction Drawings
- Communication
- Bid Management
- Financial Management



**Construction Technology** 






## **Construction Technology**

### Phoenix Project Manager

- Schedule Management
  - Monitor Progress
- Cost Management
  - Input Unit Cost
  - Labor Cost
  - Help Maintain Budget







#### Autodesk Navisworks

- 3D Rendering
  - Better Understand the Scope of Work
- Clash Detection
  - Fix scope before affecting the progress
- Collaboration
  - Coordinate trades working in the same area



## **Construction Technology**





### VR/AR Implementation

- Microsoft HoloLens & Trimble Connect
- Combining 3D modeling with real-world environments
- Encourage collaboration and facilitate real-time decisions throughout the building lifecycle



**Construction Technology** 







### **Works Cited**

- 160 VAN BRUNT, www.160vanbrunt.com/.
- Acevedo, Angélica. "First Phase of Large-Scale Redevelopment Project in Long Island City Officially Begins." *QNS.com*, 9 Dec. 2019, qns.com/2019/12/first-phase-of-large-scale-redevelopment-project-in-long-island-city-officially-begins/.
- Baird-Remba, Rebecca. "Under Construction: Urban Yard in Long Island City." *Commercial Observer*, 13 Nov. 2019, commercialobserver.com/2019/11/under-construction-urban-yard-in-long-island-city/.
- Brown, Mariah. "Elms Realty Revs Up LIC Office Redevelopment Launch." *GlobeSt*, 3 Dec. 2019, www.globest.com/2019/12/03/elms-realty-revs-up-lic-office-redevelopment-launch/?slreturn=20210122162618.
- "Elms Realty to Redevelop Long Island City Property into Urban Yard, Five-Building Complex with Office and Retail." *NYREJ*, nyrej.com/elms-realty-to-redevelop-queens-property-into-urban-yard-in-lic.
- "Floor Plans." 160 VAN BRUNT, www.160vanbrunt.com/floor-plans-1.
- Morris, By: Sebastian, and Sebastian Morris. "Newmark Knight Frank and Elms Realty Corp. to Debut Five-Building Development in Long Island City." *New York YIMBY*, 10 Dec. 2019, newyorkyimby.com/2019/12/newmark-knight-frank-and-elms-realty-corp-to-debut-five-building-development-in-long-island-city.html.
- qgazette | January 29, 2020. "Massive 'Urban Yard' Development Project Underway In LIC: Queens Gazette." Queens Gazette Massive Urban Yard Development Project Underway In LIC

  Comments, www.qgazette.com/articles/massive-urban-yard-development-project-underway-in-lic/.