

Proposal Prepared by Connect Construct

Attn: Elms Realty 40-09 21st Street Long Island City, NY 11101 Proposal Date: April 26th, 2021



624 W 139th Street, New York, NY 10031 www.connectconstruct.com 914-512-4075



April 26th, 2021

Mr. Mayer Steg Elms Realty Corp 10 Lenore Avenue Monsey, NY 10952 Re: Interior Renovation 40-09 21st Street, Long Island City, NY 11101

Dear Mr. Steg,

I hope this letter find you well, we at Connect Construct would like to thank you for the opportunity to submit our proposal to provide construction management and general contracting services to perform a full gut interior renovation for your property located at 40-09 21st Street, Long Island City, NY 11101.

Here at Connect Construct we bring over a decade of experience working in within the five boroughs of New York City and a focus on customer satisfaction that we believe is unmatched elsewhere. Our main scope of projects that we have successfully delivered throughout the lifetime of this company has been mainly focused on interior renovations of existing spaces into new state of the art facilities. We have completed projects in all five boroughs with most of our work being based in Queens. We have intimate knowledge of local building codes and ordinances as well as relationships with the local Authorities Having Jurisdiction in the borough that we have built up over time. Much of our workforce is stationed within Queens, some locally in the Long Island City neighborhood, putting us in a prime situation to focus all our resources to successfully building out your space.

We have carefully and thoroughly reviewed the RFP and construction documents provided to us thus far and are confident we can deliver this project to you in a 10-month duration schedule for a lump sum cost of \$29,711,783.36 or \$345/SqFt.

Best Regards, Devin McGettigan Founder & CEO Connect Construct devin@connectconstruct.com






Table of Contents

| Section 01 | Project Understanding and Approach | 04 |
|------------|------------------------------------|-----------|
| Section 02 | Firm Introduction | 07 |
| Section 03 | Relevant Projects | 10 |
| Section 04 | Team Organizational Chart | 16 |
| Section 05 | Project Team | 18 |
| Section 06 | CPM Project Milestone Schedule | 28 |
| Section 07 | Sample 2-Week Look Ahead | 30 |
| Section 08 | Staffing Chart | 32 |
| Section 09 | Summary Estimate | 34 |
| Section 10 | Detailed Trade Take-Off | 36 |
| Section 11 | Value Engineering Proposal | 39 |
| Section 12 | Site Logistics | 44 |
| Section 13 | Construction Site Safety Plan | 49 |
| Section 14 | Quality Assurance / Control Plan | 51 |
| Section 15 | Constructability Review | 54 |
| Section 16 | Sustainable Construction Plan | 62 |
| Section 17 | Construction Technology Initiative | 66 |
| | | |





Project Understanding and Approach





Project:

Urban City 40-09 21st Street Long Island City, NY 11101

Owner:

Mr. Mayer Steg Elm Realty 10 Lenore Avenue Monsey, NY 10952

Architect:

MSA Murdock Solon Architects 508 W 26th Street, Suite 5B New York, NY 10001 Structural Engineer: Blue Sky Design 121 W 27th Street, Suite 904 New York, NY 10001

MEP Engineer: 2LS Consulting Engineering


150 W 30th Street, 4th Floor New York, NY 10001

Interior Designer:

Input Creative Studios 58 E 11th Street, 8th Floor New York, NY 10003


Connect Construct's approach for this interior renovation of the existing six story building located at 40-09 21st Street shall be four-fold comprised of four different phases. 1. Demolition, Excavation and Foundation Work 2. Structural Upgrades (both new and existing) 3. MEPS Systems Installation 4. Interior Fit Out. These phases, in particular the final two can be scheduled and tiered in such a manner that will allow for overlap resulting in more efficient construction process and an earlier than normal completion date.

We plan on focusing all our resources and most senior personnel towards this project should we be awarded. Every aspect and detail will be met with the utmost consideration, but we plan on placing an extra emphasis on preservation of existing structural members, installing a top tier MEPS system and executing the interior finishes with the best craftsmanship there is. Should we find any underlying structural defects while beginning the renovation we shall bring it to the Owner's and Architect/Engineer's attention immediately to find the best solution for all parties.






This building is conveniently located by the East River and Long Island City & Hunters Point South Ferry Terminals as well as the Queensbridge F train stop and the Queensboro bridge putting it at the center of a major transportation hub. The total proposed floor area is 86,040 SqFt and the 1st through 6th floors are to be commercial office spaces. The 2nd through 6th floor will have access to a women's bathroom, men's bathroom, non-binary ADA bathroom and two (2) elevators.





Firm Introduction





Company:

Connect Construct 624 W 139th Street New York, NY 10031 Company Size: Annual Revenue: Average Project Cost:

95 Full-Time Staff \$65 Million \$15.5 Million

Connect Construct has been in business for 10+ years, serving the New York Metropolitan Area to meet the ever-growing needs and challenges of the construction industry. The company was founded in 2010 by Devin McGettigan who saw an opening in a rapidly growing market and envisioned a Construction Management Firm that focused primarily on serving the needs of their client, building lasting relationships and continuously helping clients connect with their goals and bring a building concept to reality as a finished product of the highest standards. Whether it be new construction or renovations and refurbishments, Connect Construct has amassed valuable experience in various sectors on the Construction Industry.

Despite being a relatively young company Connect Construct has been quite successful in building a reputation for consistently delivering on any ventures they enter into. Through a combination of bold leadership, experienced and dedicated staff, utilization of cutting-edge construction technology, and intimate knowledge of the industry both local and abroad, Connect Construct has been able to live up to its slogan, "Helping connect you to your goals".






Our self-performance capabilities position us to deliver complex, quality projects on time and within budget. Extensive knowledge of local labor forces and our client's policies and procedures gives us the ability to control key aspects of the project, particularly the early phase of the schedules. We pride our self in self-performing the Excavation, Support of Excavation, Concrete (both Foundation & Superstructure) and Masonry phases of every project we are take on. This allows us to fast track this initial, critical stage of a project and set up our subcontractors to follow with no interferences or obstructions. Our hands-on, proven management processes and experienced superintendents have led to the successful completion of numerous high-profile projects city-wide. Our people are experts in managing everything from interior renovations to complex ground up construction programs. In addition to our self-performing capabilities, we have a trusted pool of subcontractors that we repeatedly use for our projects depending on the scope. We have built up an invaluable rapport and history of successful project completion with all of our subcontractor's spanning all trades we do not self-perform. Our subcontractors are one of Connect Construct's key assets in continuing to be a successful construction company.

At Connect Construct, our goal is to foster and maintain a positive and professional work environment for all employees based on respect, trust and mutual communication. We embrace the diverse backgrounds, skills and talents of our employees and see our inclusiveness as an important, competitive advantage as we address today's business challenges proactively and effectively.





Relevant Projects





Projects Enclosed Within:

• 75 Kenmare Street (NoLita Neighborhood, Manhattan) \$28


Million Dollars

- 271 W 10th Street (West Village, Manhattan) \$8 Million Dollars
- 98-04 Queens Boulevard (Rego Park, Queens) \$25 Million

Dollars

• 12 Little W 12th Street (Meatpacking District, Manhattan) \$4

Million Dollars






Project: 75 Kenmare Street, New York, NY 10012 Client: DHA Capital Size: 77,940 SF Completion: 2019 Architect: Andre Kikoski

Connect Construct was the Construction Manager responsible for constructing this new, 7story ground up high-end luxury condominium project comprising 77,940 SF mixed used building containing 35 luxury residential unit. Connect Construct self-performed a unique top down SOE design given the site's difficult logistics and proximity to underground MTA railroad infrastructure.








Project: 271 W 10th Street, New York, NY 10014 Client: Gallium Real Estate Size: 10,250 SF Completion: 2021 Architect: S.M. Berger Architect, P.C.

Connect Construct acted as the General Contractor on this project. The scope of work was a full-scale gut renovation of an existing, historic carriage house into a luxury, one family private residence. This involved extensive underpinning of adjacent properties and SOE as we installed a new cellar space in this existing building. All finishes on this project are extremely high-end which required in-depth coordination and procurement for all trades. Currently an ongoing project and on track to meet its completion date this Summer 2021.








Project: 98-04 Queens Blvd, Rego Park, Queens, 11374 Client: DHA Capital Size: 384,630 SF Completion: 2020 Architect: SLCE Architects

Self-performed large-scale Excavation, SOE and Foundation portion for brand-new mixed-use building. Approximately 60,000 cubic yards of soil has been hauled off-site by Connect Construct and over 9,000 cubic yards of concrete was poured with 2 million pounds of rebar








in the foundation portion alone. The excavation was performed in three phases allowing the SOE to be installed periodically. Great care had to be exercised due to the proximity to MTA subway lines and adjacent buildings.

Project: 12 Little West 12th Street, New York, NY 10014 Client: 12 Little W 12th Realty Size: 6,250 SF Completion: 2020 Architect: Fifth Dimension Design


This project was a full-scale renovation to convert the top two floors of what was technically three separate buildings located in one historically landmarked structure into modern office spaces. The building needed immediate structural repairs before we could safely send personnel into the building to transform this rundown structure into appealing offices with state-of-the-art facilities.








Team Organizational Chart












Project Team








Devin McGettigan Founder & CEO

Devin McGettigan has been CEO of Connect Construct since its inception in 2010. With the help of his core original staff, Mr. McGettigan built the company from the ground up to what people see today. As President & CEO, Mr. McGettigan is responsible for project oversight throughout the life cycle of all ongoing projects from the initial bidding stage to project closeout. While Mr. McGettigan is not overseeing operations, he is out building new relationships with clients while fostering the already existing ones which is the foundation on which this company is built.








Tyler Perry Project Executive

Mr. Perry was the first employee of Connect Construct and we are proud to say he is still with us today. Starting out as the lead Project Manager on the first projects Connect Construct ever took on, Mr. Perry has worn many hats during his time at this company and is our most veteran employee. Mr. Perry's roles include general project planning, signing off on change orders, managing staff as well as managing and allocating project risk. Mr. Perry has a bachelor's degree in Construction Management from Pratt Institute as well as a master's in business administration from Columbia University.








Zaha Hadid Project Manager

Ms. Hadid is an accomplished construction project manager with more than 15 years of experience leading diverse teams and completing quality, large-scale projects of varying scopes. Ms. Hadid brings a formidable degree of expertise as well as a deep knowledge of architectural technologies and construction methods. She has worked all over the globe before coming on board at Connect Construct in 2016. Places where she has completed a plethora of buildings range from England to Hong Kong, Berlin, Tokyo, right here in New York City and many more. Ms. Hadid is one of many powerful assets among our team.








Frank Lloyd Wright Senior Project Estimator

Mr. Wright is not only our Senior Estimator here at Connect Construct but our most senior staff member as well. Mr. Wright has been involved in some of the most impressive construction projects throughout the United States and still retains his own private architectural firm while employed by Connect Construct which his currently run by his eldest son, John. Mr. Wright, having designed many buildings himself, has an intrinsic knowledge of how buildings are built and is a superb project estimator. His years of experience allows Connect Construct to prepare bids in a both accurate and expedited manner which we are extremely proud of.







Michelle Obama Site Safety Officer


Here at Connect Construct we take safety very seriously and treat it as a top priority, not only for our workers but the public as well. Ms. Obama is extremely well versed in the rules and regulations of New York City, having completed the maximum number of hours in OSHA safety certifications. In addition to being a natural born leader, Ms. Obama has an acute eye for detail ensuring that our jobsites are in pristine conditions and our workers stay out of harm's way.







Mr. Jackson is a New York City construction veteran having been in the industry for over 25 years. Mr. Jackson brings approximately 17 years of superintendent experience and has developed master skills in driving jobsite operations. Mr. Jackson possesses a unique no-nonsense attitude with an impressive degree of understanding and patience which is why he is the main liaison with our on-site subcontractors providing assistance where needed and facilitating smooth construction operations and we are honored to have him on board.








Bob Saget Project Technology Coordinator

Mr. Saget spearheads our internal technology division here at Connect Construct. Mr. Saget brings with him expertise in all the leading construction softwares and technologies including but not limited to BIM, AutoCAD, Rhino 3D as well as state of the art augmented reality softwares. As the construction industry continues to evolve rapidly these types of skills are critical to modern construction and we are proud to be able to implement these technologies in order to bring our client the best possible finished product. For this project we plan to exercise these programs for clash detection and solving constructability issues.








Amy Winehouse Assistant Project Manager

Ms. Winehouse is one of newest and most promising members to the Connect Construct family. Ms. Winehouse is a recent graduate from Pratt Institute's Construction Management Program has done great work in some of our most recently completed projects. Ms. Winehouse's tasks generally consist of scope writing, corresponding with subcontractors, leveling bids, document control as well as managing and distributing submittals and RFI's. Ms. Winehouse is there to help with whatever the project needs as well as assist the Project Manager so we can stay on top of everything.









Renzo Piano Assistant Superintendent

Mr. Piano's role as Assistant Superintendent deals with mainly site operations as well as an overview of the project schedule and updating it as necessary while coordinating with the Project Superintendent. Mr. Piano keeps close track of project progress especially that of our subcontractors and creates comprehensive daily reports which are distributed to all team members at the end of each day. Mr. Piano plays a vital role in ensuring our sites are always code compliant and clean.







CPM Project Milestone Schedule













Sample 2-Week Lookahead






2 WEEK LOOK AHEAD CONSTRUCTION SCHEDULE TEMPLATE

| | 40-09 21st Street Interior Renovation | | | | | | | | | | | | | | Date: | 6/7/2021 |
|------|---------------------------------------|----------|-------|--------|--------|---------|--------|--------|----------|--------|--------|---------|----------|---------|----------------|------------|
| | Connect Construct | - | 7-Jun | 8-Jun | 9-Jun | 10-Jun | 11-Jun | 12-Jun | 13-Jun | 14-Jun | 15-Jun | 16-Jun | 17-Jun | 18-Jun | Project Phase: | Demolition |
| Task | Construction Activity | n | M | T 2 | W 3 | TH 4 | F 5 | S 6 | Sun 7 | M 8 | Т 9 | W 10 | TH 11 | F 12 | Comments | |
| | | Duration | 1 | | | | | | | | | | | | | |
| 1 | Roof and Bulkhead Demolition | 3 days | X | | | | | | | | | | | | | |
| 2 | Roof and Bulkhead Demolition | 3 days | | X | | | | | | | | | | | | |
| 3 | Roof and Bulkhead Demolition | 3 days | | | X | | | | | | | | | | | |
| 4 | 5th & 6th Floor Demolition | 3 days | | | X | | | | | | | | | | | |
| 5 | 5th & 6th Floor Demolition | 3 days | | | | X | | | | | | | | | | |
| 6 | 5th & 6th Floor Demolition | 3 days | | | | | X | X | N/A | | | | | | | |
| 7 | 4th Floor Demolition | 2 days | | | | | | | | X | | | | | | |
| 8 | 3rd & 2nd Floor Demolition | 3 days | | | | | | | | | X | | | | | |
| 9 | 3rd & 2nd Floor Demolition | 3 days | | | | | | | | | | X | | | | |
| 10 | 3rd & 2nd Floor Demolition | 3 days | | | | | | | | | | | X | | | |





Staffing Chart






| 40-09 Int | erior Renovation | | | | | | | | | | | | 0 | | | | |
|--|--------------------|--------------------------------|------|-----------------|--------|-----------|---------|----------|----------|---------|----------|-------|-------|---------|------------------------|-----------|--|
| Interior Renovation Connect Construct | | | | | | | | | | CONNECT | | | | | | | |
| | | | | | | | | | | | | 6 | | | | | |
| Project Staffing Chart | | | | | | | | | | | | | C | CONSTRU | | | |
| | | | | Hours per Month | | | | | | | | | | | | | |
| | Employee Name | Title | June | July | August | September | October | November | December | January | February | March | April | Total | Avg Hours Per Month | % of Time | |
| | Devin McGettigan | President & CEO | 10 | 10 | 10 | 10 | 10 | 8 | 8 | 5 | 5 | 5 |) | 81 | 8.1 | 5.062 | |
| | Tyler Perry | Project Executive | 20 | 18 | 16 | 12 | 8 | 8 | 8 | 5 | 3 | 0 | | 98 | 9.8 | 6.12 | |
| | Zaha Hadid | Project Manager | 70 | 70 | 70 | 70 | 70 | 70 | 70 | 50 | 50 | 45 | | 0 635 | 63.5 | 39.687 | |
| | Amy Winehouse | Asst. Project Manager | 70 | 70 | 70 | 70 | 70 | 70 | 70 | 50 | 50 | 70 | | 0 660 | 66 | 41.2 | |
| | Frank Lloyd Wright | Senior Estimator | 25 | 25 | 15 | 15 | 10 | 5 | 5 | 0 | 0 | 0 | | 100 | 10 | 6.2 | |
| | Curtis Jackson | Project Superintendent | 160 | 160 | 160 | 160 | 160 | 160 | 160 | 160 | 160 | 160 | | 1600 | 160 | 100 | |
| | Renzo Piano | Asst. Superintendent | 160 | 160 | 160 | 160 | 160 | 160 | 160 | 160 | 160 | 160 |) | 1600 | 160 | 100 | |
| | Hank Moody | Project Engineer | 100 | 100 | 100 | 80 | 60 | 60 | 60 | 60 | 60 | 60 | | 740 | 74 | 46.2 | |
| | Michelle Obama | Site Safety Officer | 160 | 160 | 160 | 160 | 160 | 160 | 160 | 160 | 160 | 160 | | 1600 | 160 | 100 | |
| | Bob Saget | Project Technology Coordinator | C | 80 | 80 | 80 | 80 | 80 | 160 | 160 | 160 | 160 | | 0 1040 | 104 | 6 | |




Project Summary Estimate



33




Construct Connect 624 W139th Street, New York, NY 10031 CONNECT **Proposed Project Bid Summary** ONSTRUCT t you to your goals" 40-09 21st Street, Long Island City, NY 11101 **Urban Yard Interior Renovation** Division Trade/Description Item# Cost \$ /SF **Project %** 1 **Div 01 General Requirements** \$ 357,066.00 \$ 4.15 1.62% **Existing** Conditions 2 **Div 02** \$ 1,548,720.00 \$ 18.00 7.01% **Div 03** 3 Concrete \$ 1,849,860.00 \$ 21.50 8.38% 4 **Div 04** Masonry \$ 1,247,580.00 \$ 14.50 5.65% **Div 05** 5 Metals \$ 1,548,720.00 \$ 18.00 7.01% 6 **Div 06** Woods, Plastics and Composites \$ 1,062,594.00 \$ 12.35 4.81% 4.29% 7 **Div 07** Thermal and Moisture Protection \$ 11.00 946,440.00 \$ 8 **Div 08** Openings \$ 258,120.00 \$ 3.00 1.17% 9 **Div 09** Finishes \$ 2,237,040.00 \$ 26.00 10.13% 10 **Div 10** Specialties \$ 503,334.00 \$ 5.85 2.28% 11 **Div 11** Equipment \$ 43,020.00 \$ 0.50 0.19% 12 **Div 12** Furnishings \$ 30,114.00 \$ 0.35 0.14% 0.25 13 \$ 21,510.00 0.10% **Div 13** Special Construction \$ 17.50 14 **Div 14 Conveying Equipment** \$ 1,505,700.00 \$ 6.82% 15 Div 21 Fire Supression \$ 410,581.00 \$ 4.77 1.86% Div 22 \$ 8.57% 16 Plumbing 1,892,880.00 \$ 22.00 Div 23 17 Heating, Ventilating and Air-Conditioning \$ 2,473,650.00 \$ 28.75 11.20% 18 Div 26 Electrical \$ 2,280,060.00 \$ 26.50 10.33% 19 Div 27 \$ 0.38 0.15% Communications 32,695.20 \$ 20 **Div 28** Electronic Safety and Security \$ 344,160.00 \$ 4.00 1.56% 21 **Div 31** Earthwork \$ 1,161,540.00 \$ 13.50 5.26% \$ 1.25 22 Div 31 Exterior Improvements 107,550.00 \$ 0.49% 23 **Div 33** Utilities \$ 219,402.00 \$ 2.55 0.99% Trade Subtotal - Pre- General Conditions \$ 22,082,336.20 \$ 256.65 100.00% Building Permit Fees (1%) \$ 220,823.36 2.57 1.00% \$ General Conditions (5%) \$ 1,104,116.81 \$ 12.83 5.00% CM Staff (10%) \$ 2,208,233.62 \$ 25.67 10.00% Overhead and Profit (6%) \$ 1,324,940.17 \$ 15.40 6.00% Insurance (5%) \$ 1,104,116.81 \$ 12.83 5.00% Payment and Performance Bond (3%) \$ 662,470.09 7.70 3.00% \$ **Trade Total** \$ 28,707,037.06 Connect Construct CM FEE (3.5%) \$ 1,004,746.30 \$ 11.68 3.50% Total Cost with out Contingencey \$ 29,711,783.36 Contingency by Ownership (3%) \$ 891,353.50 3.00% \$ 10.36







Detailed Trade Take-off (Sprinklers)





CONNECT

CONSTRUCT "Helping connect you to your goals"


Construct Connect Detailed Trade Takeoff

624 W139th Street, New York, NY 10031 Sprinkler System

40-09 21st Street, Long Urban Yard Interior Renovation

Island City, NY 11101 Total Project SF: 86,040

| Description Quantity Unit Unit Cost Total \$ / sf Cellar New Sprinkler Piping 22.4 LF \$ 30.00 \$ 672.00 \$ 0.0 Standpipe 2 ea \$ 30,000.00 \$ 60,000.00 \$ 0.7 New Pendant Heads 3 ea \$ 50.00 \$ 150.00 \$ 0.0 Standpipe Sprinkler Piping 1093.5 LF \$ 30,000.00 \$ 90,000.00 \$ 0.3 New Sprinkler Piping 1093.5 LF \$ 30,000.00 \$ 90,000.00 \$ 1.0 New Pendant Heads 66 ea \$ 50.00 \$ 32,805.00 \$ 0.3 Standpipe 3 ea \$ 30,000.00 \$ 90,000.00 \$ 1.0 New Pendant Heads 666 ea \$ 50.00 \$ 3,300.00 \$ 0.0 New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | | | | | | | | | |
|---|--------------|--|--|--|--|--|--|--|--|
| New Sprinkler Piping 22.4 LF \$ 30.00 \$ 672.00 \$ 0.0 Standpipe 2 ea \$ 30,000.00 \$ 60,000.00 \$ 0.7 New Pendant Heads 3 ea \$ 50.00 \$ 150.00 \$ 0.0 Ground Floor New Sprinkler Piping 1093.5 LF \$ 30,000.00 \$ 0.3 Standpipe 3 ea \$ 30,000.00 \$ 0.3 Standpipe 1093.5 LF \$ 30,000.00 \$ 0.3 Standpipe 3 ea \$ 50.00 \$ 0.3 New Sprinkler Piping 1093.5 LF \$ 30,000.00 \$ 90,000.00 \$ 1.0 New Pendant Heads 66 ea \$ 50.00 \$ 3,300.00 \$ 0.0 New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | 1 0.16% | | | | | | | | |
| Standpipe 2 ea \$ 30,000.00 \$ 60,000.00 \$ 0.7 New Pendant Heads 3 ea \$ 50.00 \$ 150.00 \$ 0.7 New Pendant Heads 3 ea \$ 50.00 \$ 150.00 \$ 0.0 Ground Floor New Sprinkler Piping 1093.5 LF \$ 30,000.00 \$ 90,000.00 \$ 1.0 Standpipe 3 ea \$ 30,000.00 \$ 90,000.00 \$ 1.0 New Pendant Heads 66 ea \$ 50.00 \$ 3,300.00 \$ 0.0 New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | 0.16% | | | | | | | | |
| New Pendant Heads 3 ea \$ 50.00 \$ 150.00 \$ 0.0 Ground Floor New Sprinkler Piping 1093.5 LF \$ 30.00 \$ 32,805.00 \$ 0.3 Standpipe 3 ea \$ 30,000.00 \$ 90,000.00 \$ 1.0 New Pendant Heads 66 ea \$ 50.00 \$ 3,300.00 \$ 0.0 New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | | | | | | | | | |
| Ground Floor New Sprinkler Piping 1093.5 LF \$ 30.00 \$ 32,805.00 \$ 0.3 Standpipe 3 ea \$ 30,000.00 \$ 90,000.00 \$ 1.0 New Pendant Heads 66 ea \$ 50.00 \$ 3,300.00 \$ 0.0 New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | 70 14.61% | | | | | | | | |
| New Sprinkler Piping 1093.5 LF \$ 30.00 \$ 32,805.00 \$ 0.3 Standpipe 3 ea \$ 30,000.00 \$ 90,000.00 \$ 1.0 New Pendant Heads 66 ea \$ 50.00 \$ 3,300.00 \$ 0.0 New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | 0 0.04% | | | | | | | | |
| Standpipe 3 ea \$ 30,000.00 \$ 90,000.00 \$ 1.0 New Pendant Heads 66 ea \$ 50.00 \$ 3,300.00 \$ 0.0 New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | Ground Floor | | | | | | | | |
| Standpipe 3 ea \$ 30,000.00 \$ 90,000.00 \$ 1.0 New Pendant Heads 66 ea \$ 50.00 \$ 3,300.00 \$ 0.0 New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | 8 7.99% | | | | | | | | |
| New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | 21.92% | | | | | | | | |
| | 04 0.80% | | | | | | | | |
| | 0.06% | | | | | | | | |
| Existing Piping to Remain 583.4 LF \$ - \$ - \$ | 0.00% | | | | | | | | |
| Existing Heads to Remain 65 ea \$ - \$ - \$ - | 0.00% | | | | | | | | |
| Existing Heads to be Removed 36 ea \$ - \$ - \$ - | 0.00% | | | | | | | | |
| Single Stage Inline Fire Pump 1 ea \$ 12,000.00 \$ 12,000.00 \$ 0.1 | 4 2.92% | | | | | | | | |
| Water Supply Jockey Pump 1 ea \$ 3,500.00 \$ 3,500.00 \$ 0.0 | 0.85% | | | | | | | | |
| Remote Control Valve 8 ea \$ 450.00 \$ 3,600.00 \$ 0.0 | 04 0.88% | | | | | | | | |
| DCDA Backflow Device 1 ea \$ 9,250.00 \$ 9,250.00 \$ 0.1 | .1 2.25% | | | | | | | | |
| Siamese Connection 1 ea \$ 2,250.00 \$ 2,250.00 \$ 0.0 | 0.55% | | | | | | | | |
| Fire Hose Valve 3 ea \$ 450.00 \$ 1,350.00 \$ 0.0 | 0.33% | | | | | | | | |
| Floor Control Assembly Valve 1 ea \$ 10,000.00 \$ 10,000.00 \$ 0.1 | 2 2.44% | | | | | | | | |
| Dry Valve 1 ea \$ 450.00 \$ 450.00 \$ 0.0 | 0.11% | | | | | | | | |
| 2nd Floor | | | | | | | | | |
| New Sprinkler Piping 642.3 LF \$ 30.00 \$ 19,269.00 \$ 0.2 | 2 4.69% | | | | | | | | |
| New Pendant Heads 63 ea \$ 50.00 \$ 3,150.00 \$ 0.0 | | | | | | | | | |
| New Upright Heads 8 ea \$ 50.00 \$ 400.00 \$ 0.0 | 0 0.10% | | | | | | | | |
| Existing Piping to Remain 621.5 LF \$ - \$ - \$ - | 0.00% | | | | | | | | |
| Existing Heads to Remain 68 ea \$ - \$ - \$ - | 0.00% | | | | | | | | |
| Existing Heads to be Removed 41 ea \$ - \$ - \$ - | 0.00% | | | | | | | | |
| Fire Hose Valve 3 ea \$ 450.00 \$ 1,350.00 \$ 0.0 | 0.33% | | | | | | | | |
| Floor Control Assembly Valve 1 ea \$ 10,000.00 \$ 10,000.00 \$ 0.1 | 2 2.44% | | | | | | | | |
| 3rd Floor | | | | | | | | | |
| New Sprinkler Piping 650.3 LF \$ 30.00 \$ 19,509.00 \$ 0.2 | 4.75% | | | | | | | | |
| New Pendant Heads 65 ea \$ 50.00 \$ 3,250.00 \$ 0.0 | 0.79% | | | | | | | | |
| New Upright Heads 5 ea \$ 50.00 \$ 250.00 \$ 0.0 | | | | | | | | | |
| Existing Piping to Remain 621.5 LF \$ - \$ - \$ - | 0.00% | | | | | | | | |
| Existing Heads to Remain 68 ea \$ - \$ - \$ - | 0.00% | | | | | | | | |
| Existing Heads to be Removed 41 ea \$ - \$ - \$ - | 0.00% | | | | | | | | |
| Fire Hose Valve 3 ea \$ 450.00 \$ 1,350.00 \$ 0.0 | | | | | | | | | |
| Floor Control Assembly Valve 1 ea \$ 10,000.00 \$ 10,000.00 \$ 0.1 | | | | | | | | | |






| | | 4t | h Floor | | | | |
|------------------------------|-------|------|---------|-----------|-----------------|------------|-------|
| New Sprinkler Piping | 521.1 | LF | \$ | 30.00 | \$ 15,633.00 | \$ 0.18 | 3.81% |
| New Pendant Heads | 64 | ea | \$ | 50.00 | \$ 3,200.00 | \$ 0.04 | 0.78% |
| New Upright Heads | 5 | ea | \$ | 50.00 | \$ 250.00 | \$ 0.00 | 0.06% |
| Existing Piping to Remain | 505.3 | LF | \$ | - | \$ - | \$ - | 0.00% |
| Existing Heads to Remain | 68 | ea | \$ | - | \$ - | \$ - | 0.00% |
| Existing Heads to be Removed | 41 | ea | \$ | - | \$ - | \$ - | 0.00% |
| Fire Hose Valve | 3 | ea | \$ | 450.00 | \$ 1,350.00 | \$ 0.02 | 0.33% |
| Floor Control Assembly Valve | 1 | ea | \$ | 10,000.00 | \$ 10,000.00 | \$ 0.12 | 2.44% |
| | | 5tl | h Floor | | | | |
| New Sprinkler Piping | 515.8 | LF | \$ | 30.00 | \$ 15,474.00 | \$ 0.18 | 3.77% |
| New Pendant Heads | 64 | ea | \$ | 50.00 | \$ 3,200.00 | \$ 0.04 | 0.78% |
| New Upright Heads | 5 | ea | \$ | 50.00 | \$ 250.00 | \$ 0.00 | 0.06% |
| Existing Piping to Remain | 505.6 | LF | \$ | - | \$ - | \$ - | 0.00% |
| Existing Heads to Remain | 68 | ea | \$ | - | \$ - | \$ - | 0.00% |
| Existing Heads to be Removed | 41 | ea | \$ | 2 | \$ <u></u> | \$ - | 0.00% |
| Fire Hose Valve | 3 | ea | \$ | 450.00 | \$ 1,350.00 | \$ 0.02 | 0.33% |
| Floor Control Assembly Valve | 1 | ea | \$ | 10,000.00 | \$ 10,000.00 | \$ 0.12 | 2.44% |
| | | 6t | h Floor | | | | |
| New Sprinkler Piping | 711.9 | LF | \$ | 30.00 | \$ 21,357.00 | \$ 0.25 | 5.20% |
| New Pendant Heads | 63 | ea | \$ | 50.00 | \$ 3,150.00 | \$ 0.04 | 0.77% |
| New Upright Heads | 5 | ea | \$ | 50.00 | \$ 250.00 | \$ 0.00 | 0.06% |
| Existing Piping to Remain | 621.8 | LF | \$ | - | \$ - | \$ - | 0.00% |
| Existing Heads to Remain | 68 | ea | \$ | - | \$ - | \$ - | 0.00% |
| Existing Heads to be Removed | 41 | ea | \$ | Ξ. | \$ - | \$ - | 0.00% |
| Fire Hose Valve | 3 | ea | \$ | 450.00 | \$ 1,350.00 | \$ 0.02 | 0.33% |
| Floor Control Assembly Valve | 1 | ea | \$ | 10,000.00 | \$ 10,000.00 | \$ 0.12 | 2.44% |
| | | Roof | Bulkhea | nd | | | |
| New Sprinkler Piping | 70.4 | LF | \$ | 30.00 | \$ 2,112.00 | \$ 0.02 | 0.51% |
| New Pendant Heads | 7 | ea | \$ | 50.00 | \$ 350.00 | \$ 0.00 | 0.09% |
| New Upright Heads | 1 | ea | \$ | 50.00 | \$ 50.00 | \$ 0.00 | 0.01% |
| Fire Hose Valve | 3 | ea | \$ | 450.00 | \$ 1,350.00 | \$ 0.02 | 0.33% |
| Floor Control Assembly Valve | 1 | ea | \$ | 10,000.00 | \$ 10,000.00 | \$ 0.12 | 2.44% |
| 3-Way Manifold | 3 | ea | \$ | 600.00 | \$ 1,800.00 | \$ 0.02 | 0.44% |
| | | | | | | | |
| Total Sprinkler Cost | | | | \$ | | 410,581.00 | |



Value Engineering Proposal






Value Engineering: Also known as a value analysis, is the process of evaluating documented design to identify potential alternative methods, systems, or materials that will benefit the owner by enhancing the life cycle of the project." – CSI PRM 4.7.7

At Connect Construct, we like to review every set of construction documents that come our way and perform an in-house analysis on how we can offer some value engineering options to the owner to save money and/or time while maintaining the desired quality.

Value engineering relies heavily on team building, effective communication, and efficient decision making to reach creative solutions. By working together, we are able to arrive at unique approaches to specific design elements to satisfy your project vision and save you money on the project cost.

Just a brief history on value engineering, the process can be dated to World War II. General Electric first introduced the process which they called Value Analysis. Due to the shortage of materials in that period, the company need to find substitute. As they found options that were available, cost less, and performed equally well or better, Value Analysis became a process inherent in their operational approach. Keeping in spirit with this, Connect Construct has






maintained an ethos of keeping value analysis/engineering as an inherent element in our project approach.

After General Electric successfully made this part of their operational approach, the US Navy then realized they could benefit by using Value Analysis and approached General Electric for collaboration with their engineering resources. Following the war, the Navy began to use Value Analysis, taught it to their naval officers, and changed the terminology to Value Engineering.


Based on our review of the construction documents provided, our value engineering proposal is as follows.

There is always money to be saved on the finishes specified for a project, however, due to the white box approach to this project the majority of the finishes existing in the building core at the elevator lobbies. We did not want to change too much aesthetically with this space as it will make up much of the architectural character of the finished space. We recommend the Elkay SwirlFlo ERPBM28K fountain. There is substantial cost savings to be found here while keeping the same general aesthetic for the water foundation. Through working with our long-time plumbing fixture suppliers we were able to find a discounted product for the same quality.















Site Logistics









624 W 139th Street, New York, NY 10031


















45




CONNECT

Ground Floor Site Logistics Plan



Quality Assurance / Control Plan






Here at Connect Construct, we are committed to providing top quality work and a large part of ensuring that we stay consistent is our robust Quality Assurance/Control program that we implement for all our projects. Quality Assurance and Quality Control play a crucial role in delivering a finished product that we can be proud to turn over to the owner and the owner can be proud to own for the years to come. Unfortunately, if QA/QC are not properly administered, it can result in construction defects ultimately having negative impacts when it comes to getting the building suitable for occupancy. Thankfully, Connect Construct is a firm that stands by our quality assurance and quality control procedures and through our decades of experience working in New York City and beyond we have gained invaluable experience and have been able to develop a tried and tested QA/AC program that we bring to all our projects and would like to overview.

What defines quality? What quality means to us can be simplified to basically meaning fitness to be used and conformance to the design requirements. Quality assurance is a proactive process that focuses on the processes utilized to ensure this. There are always unforeseen issues that come with construction this much cannot be avoided, this is why we have measures in place to reduce and prevent issue before they arise and mitigate them successfully if and when they do arise.

Key components of our quality assurance process:

<u>Submittals:</u> Submittals are the key in quality assurance. For all aspects of the nob we thoroughly vet the design requirements and intentions laid forth in the construction documents and we organize all the product information and procedures into easy to






understand documentation and submit to the design team for review and approval prior to any work taking place for this and materials getting to the jobsite. This way, we are able to ensure everybody is on the same page and we have a comprehensive record to check back to for what should be on the project. We plan to use Procore as our project management software so the owner, design team and all subcontractors can use one platform to access all project information.

Mockups and Samples: This is part of the submittal process as well. For certain key components of the project, we can provide physical examples of what the work will look like when fully installed for review and approval so we can agree on the finished outcome before it even ever gets started. All required parties will be able to tangibly see what the construction will look like based on design before the construction is completed. Mockups will be able to be tested and once fully approved serve as a benchmark for construction quality so the work can be streamlined once ready to begin.

<u>Certification and Warranties</u>: Manufacturer certifications are required for applicable products and materials to ensure the products used have been installed properly to guarantee the best possible functioning systems have been installed. All certifications and approvals are to be comprehensively documented for the owner's satisfaction. For all applicable products we plan to procure warranties in the owner's name to guarantee quality of the product installed and a warranty to repair for the years to come.

Quality control relies on the continuous verification of products, systems, and procedures of what is installed. Once we have everything approved the quality of what






is to be built is approved and assured, we have to monitor and control it throughout the life cycle of the project to make sure it is adhered to and guarantee it is consistent with what we planned for and approved. Quality control will be executed by our superintendent and management field personnel.

Delivery Inspections: All material brought to the jobsite will be inspected for damage prior to being brought into the building and will be double checked to make sure is as per the specifications we ordered. This way we can monitor and control everything that comes into the building and is installed and also makes sure there was no mistakes made along the way and we receive the wrong product.

Testing & Inspections: As per the TR-1 created and filed by the design applicant with the NYC Department of Buildings, all the required tests and inspections will be carried out by a licensed testing company to ensure that all required approvals are retained and completed before moving on to the next stage of work. Without all the required inspections a certificate of occupancy cannot be issued which we will never allow to happen.


Daily Reports and Field Inspections: Every single day our superintendent creates a daily report of all the work completed that day including all deliveries, site visitors and inspections carried out. This report will be circulated with the project team to everybody stays up to date and can monitor progress. Multiple times throughout the day the super walks the entire project to monitor progress and ensure everything is staying on schedule and the work is being carried out correctly.







Site Safety Plan






Connect Construct Site Safety Plan 40-09 21st Street, Long Island City, NY 11101

Here at Connect Construct we believe that no job or no task is more important than worker health and safety. Due to the nature of the industry, site operations often pose inherent risks to the individuals involved. When it comes to identifying the most hazardous occupations in the USA, working in construction ranks very high on the list. Responsible for 20percent of work-related deaths in 2020, the construction industry is known to pose several risks for workers. If a job represents a potential safety or health threat, every effort will be made to plan a safe way to do the task.


We can proudly say at Connect Construct we have never had a work-related injury on any of our projects. With an Experience Modification Rate (EMR) of 0.79 we are well below the national industry average rating for construction companies. We attribute our low rating to the various safety methods we routinely implement on all our sites and that we hope to implement on yours. On the following page we have listed the safety procedures we plan to bring to Urban Yard as well as some of the safety risks we have identified.





Safety Procedures:

- All workers supplied with PPE. Any field personnel are equipped with state-of-the-art PPE. Surplus PPE is always kept onsite in case somebody is without one of the essential items.
- COVID screening upon entry to site. Workers that have high temperatures or exhibit symptoms will be sent home immediately and be required to produce a negative COVID test before returning.
- Fall protection always provided for workers working near ledges or at any heights above 5 feet.
- We plan to provide a Site Safety Officer on this project at no additional cost to the owner. Under NYC DOB & OSHA safety regulations we are not required to provide a Site Safety Officer but as an example of our commitment to site safety we plan to provide one anyways.
- Toolbox talks held daily every morning regarding the tasks to be done that day.
- Sign in sheet at entrance. Workers will be required to sign their name in every morning and sign on the way out so we can keep track of entry/exit times.






Project Safety Risks:

- 1. We have determined that the elevator shaft work poses certain risks to both the concrete and the elevator workers. To mitigate this risk, we shall ensure every worker working in this area will be equipped with fall protective gear and is always tied off to prevent anybody from falling down the shafts.
- 2. Fires resulting from hot work activity. Hot work is any work that creates sparks or uses an open flame to work such as grinding/cutting metal and welding. To mitigate this risk we require that prior to beginning any hot work, workers are required to come to the field office and get themselves a "hot work permit". They will be required to fill this out and return to us every time before beginning work. Workers will also be required to supply a licensed fire guard to supervise work and properly prepare the area for hot work so no conditions for a fire to start are present.
- 3. Another risk we identified his the hoist/lifting of material from the exterior of the building by the use of a crane or other hoist equipment. This creates a risk to the public as well as workers due to the heavy items above them. To mitigate this risk we plan to supply licensed flaggers on a minimum of two sides of the material hoisted to direct/stop traffic as well as direct pedestrians. Prior to each pick (lift) of materials we will use an airhorn to indicate the pick is about to begin.



Constructability Review





For us at Connect Construct, constructability reviews are crucial elements of the preconstruction phase we like to put an emphasis on. This can be critical to ensuring a successful project by identifying and eliminating any potential discrepancies that can become an issue down the road. A constructability review is a process we use during the bidding and preconstruction phases that allows us to infuse or construction knowledge into the design process. We noticed two discrepancies in the 90% Construction Document Set dated 10/28/20 that we have received thus far and based our overall project proposal on.

Included in the following pages are two RFI's we have submitted to the design team to date based on the roof construction and bulkhead masonry curtain wall construction and supplementary constructability reviews based on our findings.

1. <u>RFI #001 – Roof Construction Design</u>

It is unclear in the drawings provided whether the roof construction is to be new or if there is an existing membrane to remain. Both options will require further information and input from the design team. If the roof is to remain then it is necessary to know if it needs any repairs which would be contingent on when the existing membrane was installed and the system that was installed. Roofs generally need repaired or replaced every 20 years on average. If there is to be a new roof membrane installed then Connect Construct will need to know the desired manufacturer, R-Value requirements, and warranty requirements. For both options, existing and new, we will need further details for roof penetrations and pitch pockets.

2. RFI #002 - Bulkhead Masonry Curtain Wall

There is further information required for the construction of the masonry curtain wall cladding for the new rooftop bulkhead. Clarification is needed on the type of brick (size, pattern, colors, manufacturer, grade) as well as general masonry curtain wall such as brick ties and horizontal reinforcement.



RFI Transmittal

Request for Information # 001

Project:

Urban Yard 40-09 21st Street Long Island City, NY 11101

Submitted To: MSA Murdock Solon Architects 508 W 26th Street Suite 5B New York, NY 10003 Submitted By: Connect Construct 624 W 139th Street Suite 4D New York, NY 10031

| Subject | Discipline | Co-Author | Reference Information |
|-------------|------------|-----------|------------------------|
| Roof Design | Roofing | | Architectural Drawings |

Information Requested

Please provide more information regarding roof design for construction. The drawings provided are not clear on whether there is a new membrane being installed or if the existing is staying.

If existing stays: Are there any repairs needed? Has there been a history of leaks? Please provide details for roof penetrations and pitch pockets.

If there is new roof: Please provide specifications for desired system. Please provide details for roof penetrations and pitch pockets. ENGINEER/ ARCHITECT RESPONSE

Your immediate response is required to avoid delays in detailing, engineering, fabrication, and installation.

Answered by:

Date Answered:



57

Initiated Date: 3.8.21

Response Required By: 3.22.21



RFI Transmittal

Request for Information # 002

Project:

Urban Yard 40-09 21st Street Long Island City, NY 11101

Submitted To: MSA Murdock Solon Architects 508 W 26th Street Suite 5B New York, NY 10003

Submitted By: Connect Construct 624 W 139th Street Suite 4D New York, NY 10031

| Subject | Discipline | Co-Author | Reference Information |
|---------------------------|---------------|-----------|------------------------|
| Bulkhead Exterior Masonry | Brick Masonry | | Architectural Drawings |

Information Requested

Please provide more information regarding masonry curtain wall at roof bulkhead exterior. Additional information required for brick type/design, desired manufacturer, specified brick ties and waterproofing/vapor barrier system.

ENGINEER/ ARCHITECT RESPONSE

Your immediate response is required to avoid delays in detailing, engineering, fabrication, and installation. Answered by:

Date Answered:




58

Initiated Date: 3.8.21

Response Required By: 3.22.21



Sustainable Construction Plan






Why is sustainable construction important?

The construction industry makes up for roughly 6.36% of the American GDP. There are numerous smaller industries that ultimately make up the construction industry, such as builders (specialized and general), material manufacturers, raw material resourcing, refinement, and production just to name a few. Earth is made up of finite resources and has a rapidly growing population. The demand for resources in construction is considerable. As we move towards a more sustainable future, construction is one of the most important industries related to this sustainable revolution. Sustainable construction is not just about the creation of a building that has a low environmental impact; it is a new approach in the building sector that improves the way people live and build.

How does construction affect climate change?

Poorly designed and constructed buildings use more energy, increasing the demand on energy production and contributing to global warming. Reducing energy use in buildings is one of the most important ways to reduce human's overall environmental impact.

For example: Concrete. Concrete is the most widely used artificial material in existence. The only thing we consume more of is water. Concrete is a major contributor to the climate crisis because its production releases huge






quantities of carbon dioxide into the atmosphere. Carbon dioxide are the two greenhouse gases most responsible for global warming. The carbon dioxide emissions from the production of concrete are so high that if concrete were a country, it would be the third largest emitter of CO2 behind China and the United States.

Based on the construction documents provided there are no sustainability requirements set forth this project. Generally, there are additional costs associated with achieving higher certifications of sustainable construction (LEED Gold, Platinum, etc) due to the increased regulation and higher standard of materials. For the Urban Yard project, we plan to take extra care to employ sustainable measures when and where we can but ultimately there are no increased costs to be experience due to sustainability requirements. Several of our project managers and company leadership are LEED Certified. Connect Construct has completed several projects with varying degrees of LEED requirements. Much of our personnel has sat the LEED certification exam for individuals and are familiar with the ins and outs of sustainable construction and how to employ it during construction.


Some sustainable measures we plan to employ on this project are as follows.

• Dust control measures (Hoses for spraying water while using cutting tools and for other dust-creating work. We will also use dust collecting attachments on as many tools as possible)






- Follow Commissioning requirements laid out in LEED v4 "Energy and Atmosphere, Prerequisite 1, Fundamental Commissioning and Verification
- Waste management service that picks up trash containers multiple times a week, sorts through trash and disposes of accordingly. Controls where the trash goes. (Recycling, etc)
- Develop and implement indoor air quality (IAQ) management plan for the construction and preoccupancy phases of the building.
- Noise control / reduction. Work only to take place during approved permit hours to reduce disruption to neighborhood.







Construction Technology Initiative






Connect Construct Technology Initiative:

Now more than ever, technology is transforming the construction industry and the need for technologically competent contractors is self-evident. Here at Connect Construct, we pride ourselves on staying up to date with the latest technology innovations and implementing them in our day-to-day operations. We employ a variety of programs and softwares that enable us to administer and deliver projects ahead of expectations. We use these technologies for cost management, scheduling, daily reporting, tracking progress, quality control and quality assurance. Doing so allows up to improve efficiency and track our projects in real time throughout the entire life cycle allowing us to better manage the project. All of our employees are proficient with the technology that we implement and below is a synopsis on what we would like to bring to your project.

Procore:

We use Procore as a one stop shop for carrying out project management duties from preconstruction to closeout. This platform allows us to manage submittals and RFI's through a medium that allows all project team members access creating a flow of continuity for the project. Everyone can always see when things have been submitted, when due dates are scheduled, and all pertinent information shared via responses and approvals. In addition to this Procore acts as a construction drawing management tool. Here, all project members can see what the most up to date drawing sets are and use a built-in tool to see what has changed from previously issued drawing sets, if any. Procore also allows for the distribution of meeting minutes and project reporting. Having everybody on the same page is critical for a successful project and this is one of the resources we use to ensure this.





Planswift On Screen Takeoff:


Planswift is the industry's leading OST (On Screen Takeoff) software. All of our employees come equipped with this program and it is what we use to perform quantity takeoffs and put together estimates ranging from our initial base bid or for proposals for any work outside of the project scope. This tool allows to get the most accurate quantity estimates and generate reports in a timely manner that is simply not available to somebody using the traditional methods of performing takeoffs by hand.

Revit Autodesk:

This is a software tool we use for Building Information Modeling, also known as BIM. Through Revit we create realistic 3D models of the building, that can be used for clash detection and help expedite the fabrication process. Through the use of this tool, we can build the building in a virtual space and work through any potential issues so that when it comes time for construction in the field we are better able to execute the design in a more efficient and safe manner.


Microsoft Project:

This is our scheduling software we use to create our project schedules to use and follow throughout the project life cycle. We are continuously updating and maintaining our project schedules, directly from Microsoft Project we are able to export the schedule file and distribute directly to the owner, trade subcontractors, and all other relevant personnel. This software offers various in-depth analysis tools and reports that can be generated so you we can monitor project progress and all times and provide comprehensive reports and updates to the owner.





Works Cited






Works Cited

- 1. MSA Architects, https://murdocksolon.com/
- 2. <u>2L Engineering, https://www.2lmep.com/</u>
- 3. <u>Blue Sky Design</u>, <u>http://www.blueskydsgn.com/5na9xfgabm2787hj4iagf2z7bqe4gg</u>
- 4. <u>Under Construction: Urban Yard in Long Island City,</u> https://commercialobserver.com/2019/11/under-construction-urban-yard-inlong-island-

<u>city/#:~:text=A%20collection%20of%20decaying%20warehouses,launch%20lea</u> <u>sing%20for%20office%20tenants.</u>


- 5. <u>Urban Yard Development Project, https://www.qgazette.com/articles/massive-urban-yard-development-project-underway-in-lic/</u>
- 6. <u>Elm Realty to redevelop Long Island City Property, https://nyrej.com/elms-</u> <u>realty-to-redevelop-queens-property-into-urban-yard-in-lic</u>
- 7. <u>Constructability Reviews CMAA</u>, <u>https://www.cmaanet.org/sites/default/files/resource/Constructiblity%20Revie</u> <u>ws.pdf</u>
- 8. <u>CM Proposal Tips, https://www.procrewschedule.com/8-tips-on-writing-</u> winning-construction-project-bids/





- 9. <u>Sustainability in CM, https://www.pmi.org/learning/library/sustainability-</u> construction-industry-7099
- 10. <u>Sustainable Construction Management</u>, <u>https://www.sciencedirect.com/science/article/abs/pii/S0959652620303978</u>
- 11. Interior Renovation Guide, https://aquilacommercial.com/pillar/theultimate-guide-to-building-out-office-space/
- 12. <u>Construction Technology 2021, https://www.bigrentz.com/blog/construction-</u> <u>technology</u>
- 13. Construction Technology Trends,

https://www.constructionbusinessowner.com/technology/13-constructiontechnology-trends-watch





Urban Yard Elms Realty 40-09 21st Street Long Island City, NY 11101 <u>Proposal Date:</u> April 26th, 2021 <u>Prepared By:</u> Connect Construct

CONNECT ONSTRUCT "Helping connect you to your goals"



- Project Understanding and Project Approach
- Firm Background
- Project Team
- Staffing
- Preliminary Project Schedule
- Project Cost Summary
- Detailed Take Off
- Site Logistics

Agenda

- Value Engineering
- Constructability
- Quality Assurance & Quality Control
- Site Safety
- Sustainability
- Construction Technology Initiatives
- Visual Presentation
- Work Cited

Project Directory

Project:

Urban City

40-09 21st Street

Long Island City, NY 11101

Owner:

Mr. Mayer Steg

Elm Realty

10 Lenore Avenue

Monsey, NY 10952

Architect:

MSA Murdock Solon Architects 508 W 26th Street, Suite 5B New York, NY 10001



Structural Engineer:

Blue Sky Design 121 W 27th Street, Suite 904 New York, NY 10001

MEP Engineer:

2LS Consulting Engineering 150 W 30th Street, 4th Floor New York, NY 10001

Interior Designer:


Input Creative Studios 58 E 11th Street, 8th Floor New York, NY 10003



Input

CREATIVE STUDIO

Project Understanding



Project Requirements:

Excavation in Cellar & Ground floor.

New MEPS System

Two (2) new elevators

New interior finishes

Additional structural members

Interior/Exterior Signage

New stairwell

Interior Renovation Rooftop MEP Equipment New Restrooms New Building New Building White-Box Interior Fit-Out

| 0 | Mode | Task Name | Duration | | | Predecessors | Resource Names | Qtr 2, 2021 Apr | | May | T | Jun | Qtr 3, 2021 Ju | ul | Aut | 1 | Sep | Qtr 4, 20 | 21 0a | 1 | Nov | Da | к | Qtr 1, 2022 Ja | 0 | Feb | Ма | ¥ | Qtr 2, 2022 Apr | N | lay | 1 |
|----------|----------|--------------------------------|----------|--------------|---------------------------|--------------|----------------|--------------------|--------|-----|-------|-----|-------------------|----|-----|---|-----|-----------|----------|---|-----|----|---|-------------------|---|-----|----|---|--------------------|---|-----|------|
| 1 | | Proposal Submission | 0 days | Mon 4/26/21 | Mon 4/26/21 | | | | ¢ 4/26 | | | | | | | | | | | | | | | | | | | | | | | |
| 2 ; | * | Project Award | 1 day | Thu 5/6/21 | Thu 5/6/21 | 1 | | | 1 | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | t | Bid Process (Fast Track) | 6 days | Fri 5/7/21 | Fri 5/14/21 | 2 | | | ì | * | | | | | | | | | | | | | | | | | | | | | | |
| 4 | 1 | Level Bids | 7 days | Wed 5/12/21 | Thu 5/20/21 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | ŧ | Award Subcontractors | 4 days | Tue 5/25/21 | Fri 5/28/21 | 4 | | | | 1 | | | | | | | | | | | | | | | | | | | | | | |
| 6) | * | Shop Drawing & Submittals | 25 days | Thu 5/27/21 | Wed 6/30/21 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | h | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | 1 | Project Commencement | 0 days | Tue 6/1/21 | Tue 6/1/21 | | | | | | ♦ 6/1 | | | | | | | | | | | | | | | | | | | | | |
| | 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | 1 | | 4 days | Tue 6/1/21 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 11) | * | Equipment/Material Delivery | 4 days | Tue 6/1/21 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 12 | * | Install Sidewalk Bridge | 1 day | Wed 6/2/21 | Wed 6/2/21 | | | | | | - | | | | | | | | | | | | | | | | | | | | | |
| 13 | * | Install Exterior Pipe Scaffold | 2 days | Thu 6/3/21 | Fri 6/4/21 | 12 | | | | | ŭ | | | | | | | | | | | | | | | | | | | | | |
| | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 15 | | Demolition/Excavation | 16 days | Mon 6/7/21 | Mon 6/28/21 | | | _ | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| 11128 | 7 | | | | | | | _ | | | | | | | | | | | | | | | | | | | | | | | | |
| | t | Concrete | 34 days | Tue 6/29/21 | Fri 8/13/21 | | | _ | | | | | | | | | | | | | | | | | | | | | | | | |
| 1991 - H | 7 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | * | Masonry | 25 days | Thu 7/15/21 | Wed 8/18/21 | _ | _ | | | | | | 1 | | | I | | | | | | | | | | | | | | | | |
| | 7 | | | | | | _ | - | | | | | | | | | | | | | | | | | | | | | | | | |
| 21 | 1 | Structural Steel | 24 days | Thu 7/22/21 | Tue 8/24/21 | | | - | | | | | | | | | | | | | | | | | | | | | | | | |
| | 4 | | | | r Lanlan lac | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 1 | Elevator | 45 days | Mon 8/30/21 | Fn 10/29/21 | | - | - | | | | | | | | | | | | | | | | | | | | | | | | |
| 24 | \$ | A 10 0 A | | a alasta | * 1 4 6 (4 = 14 - | | | - | | | | | | | | | | | | | | | | | | | | | | | | |
| | * | Ground Floor Fit Out | 45 days | Mon 8/16/21 | Fn 10/15/21 | | | - | | | | | | | | | | | | | | | | | | | | | | | | |
| | | A-10 | | Turnalister | T 44 Jac Inc | | - | - | | | | | | | | | | | | | | | | | | | | | | | | |
| 27 28 | | 2nd Floor Fit Out | 46 days | Tue 9/14/21 | Tue 11/16/21 | | - | - | | | | | | | | | | | | | | | | | | | | | | | | |
| 28 29 | 5 | A.17. C.A. | | * | • ' • • ! • • ! • · ! • · | | | - | | | | | | | | | | | | | | _ | | | | | | | | | | |
| | <u>۲</u> | 3rd Floor Fit Out | 44 days | Tue 10/12/21 | FN 12/10/21 | - | - | - | | | | | | | | | | | | | | | | | | | | | | | | |
| 30 | 7 | 4th Floor Fit Out | A2 dave | Thu 11/11/14 | 5117/22 | | - | - | | | | | | | | | | | | | | | | | | | | | | | | |
| | x 5 | 401 FILOUT FILOUT | 42 days | Thu 11/11/21 | rn 1/1/22 | | | - | | | | | | | | | | | | | | | | | | | | | | | | |
| 32 | | Eth Floor Fit Out | A0 dave | Tuo 12/14/24 | 5-2/10/22 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | ¥ 5 | 5th Floor Fit Out | 49 days | Tue 12/14/21 | 11 2/18/22 | | _ | - | | | | | | | | | | | | | | | | | | | | | | | | |
| 35 | | 6th Floor Fit Out | 50 dave | Wed 1/20/21 | Tue 2/20/21 | | | - | | | | | | | | | | | | | | | | | | | | | | | | |
| | x 5 | our noor nit out | 50 days | weu 1/20/21 | 100 3/ 30/21 | | | - | | | | | | | | | | | | | | | | | | | | | | | | |
| 37 | | Roof /Bulkhead | 24 days | Thu 1/20/22 | Tue 2/22/22 | | | | | | | | | | | | | | | | | | | | _ | | | | | | | |
| | * 5 | nooi / Buikneau | 24 days | 110 1/20/22 | 100 2/22/22 | | - | - | | | | | | | | | | | | | | | | | | | | | | | | |
| | | Class Out Process | 25 daur | Map 2/20/22 | Fri 4/1/22 | | | - | | | | | | | | | | | | | | | | | | | | | | | | |
| 19 | * | Close Out Process | 25 days | Mon 2/28/22 | 114/1/22 | | | | | | | | | | | | | | | | | | | | | | | | - | | | |

2 WEEK LOOK AHEAD CONSTRUCTION SCHEDULE TEMPLATE

| | 40-09 21st Street Interior Renovation | | | | | | | | | | | | Date: | |
|------|---------------------------------------|----------|-------|-------|-------|--------|--------|--------|--------|--------|--------|--------|----------------|---|
| | Connect Construct | | 7-Jun | 8-Jun | 9-Jun | 10-Jun | 11-Jun | 14-Jun | 15-Jun | 16-Jun | 17-Jun | 18-Jun | Project Phase: | |
| Task | Construction Activity | Duration | М | T | W | TH | F | М | T | W | TH | F | Commonts | Ĺ |
| Lask | Construction Activity | Duration | 1 | 2 | 3 | - 4 | 5 | 8 | 9 | 10 | 11 | 12 | Comments | |
| 1 | Roof and Bulkhead Demolition | 3 days | X | | | | | | | | | | | |
| 2 | Roof and Bulkhead Demolition | 3 days | | X | | | | | | | | | | |
| 3 | Roof and Bulkhead Demolition | 3 days | | | X | | | | | | | | | |
| 4 | 5th & 6th Floor Demolition | 3 days | | | X | | | | | | | | | 1 |
| 5 | 5th & 6th Floor Demolition | 3 days | | | | X | | | | | | | | 1 |
| 6 | 5th & 6th Floor Demolition | 3 days | | | | | X | | | | | | | 1 |
| 7 | 4th Floor Demolition | 2 days | | | | | | X | | | | | | 1 |
| 8 | 3rd & 2nd Floor Demolition | 3 days | | | | | | | X | | | | | 1 |
| 9 | 3rd & 2nd Floor Demolition | 3 days | | | | | | | | X | | | | 1 |
| 10 | 3rd & 2nd Floor Demolition | 3 days | | | | | | | | | X | | | 1 |

2 Week Look Ahead

Introduction: Connect Construct Firm Intro

- Founded in 2010
- Company Size
 - \$65 Million Annually
 - 95 Employees
- <u>Client satisfaction</u> and <u>safety</u> top priorities
- HQ in Uptown Manhattan/West Harlem
- Self performs Excavation, SOE, Concrete & Masonry



40-09 Interior Renovation Interior Renovation Connect Construct Project Staffing Chart



| | | | Avg Hours | |
|--------------------|--------------------------------|-------|-----------|-----------|
| Employee Name | Title | Total | Per Month | % of Time |
| Devin McGettigan | President & CEO | 81 | 8.1 | 5.0625 |
| Tyler Perry | Project Executive | 98 | 9.8 | 6.125 |
| Zaha Hadid | Project Manager | 635 | 63.5 | 39.6875 |
| Amy Winehouse | Asst. Project Manager | 660 | 66 | 41.25 |
| Frank Lloyd Wright | Senior Estimator | 100 | 10 | 6.25 |
| Curtis Jackson | Project Superintendent | 1600 | 160 | 100 |
| Renzo Piano | Asst. Superintendent | 1600 | 160 | 100 |
| Hank Moody | Project Engineer | 740 | 74 | 46.25 |
| Michelle Obama | Site Safety Officer | 1600 | 160 | 100 |
| Bob Saget | Project Technology Coordinator | 1040 | 104 | 65 |





Relevant Projects

- 271 W 10th Street (West Village, Manhattan) \$8 Million Dollars
- 75 Kenmare Street (NoLita Neighborhood, Manhattan)
 \$28 Million Dollars
- 12 Little W 12th Street (Meatpacking District, Manhattan) \$4 Million Dollars
- 98-04 Queens Boulevard (Rego Park, Queens) \$25 Million Dollars



Project: 271 W 10th Street, New York, NY 10014 Client: Gallium Real Estate Size: 10,250 SF Completion: 2021 Architect: S.M. Berger Architect, P.C.

- Full-scale gut renovation of an existing, landmarked historic carriage house into a luxury, one family private residence.
- Involved extensive underpinning of adjacent properties and SOE as we installed a new cellar space in this existing building.
- New elevator
- New MEP systems
- Very high-end finishes



Project: 75 Kenmare Street, New York, NY 10012 Client: DHA Capital Size: 77,940 SF Completion: 2019 Architect: Andre Kikoski

- New, 7-story ground up high-end luxury condominiums.
- Connect Construct self-performed

 a unique top down SOE design
 given the sites difficult logistics
 and proximity to underground
 MTA railroad infrastructure.

Project: 12 Little West 12th Street, New York, NY 10014 Client: 12 Little W 12th Realty Size: 6,250 SF Completion: 2020 Architect: Fifth Dimension Design

- Full-scale renovation of existing, historically landmarked structure into modern office spaces.
- New MEP systems
- Extensive structural repairs were necessary before we could safely send personnel into the building to transform this rundown structure into appealing offices with state-of-the-art facilities





Project: 98-04 Queens Blvd, Rego Park, Queens, 11374 Client: DHA Capital Size: 384,630 SF Completion: 2020 Architect: SLCE Architects

- Self-performed large-scale Excavation, SOE and Foundation portion for brand-new mixed-use building.
- Approximately 60,000 cubic yards of soil removed by Connect Construct
- 9,000 cubic yards of concrete poured with 2 million pounds of rebar in the foundation portion alone.





Interior Renovation Bid Summary

<u>Total Cost:</u> \$29,711,783.36

<u>Cost per SF:</u> \$345.33/sf Construct Connect 624 W139th Street, New York, NY 10031 Proposed Project Bid Summary



40-09 21st Street, Long

Island City, NY 11101 Urban Yard Interior Renovation

| Total Proje | ud SF: 86,040 SF 👘 | | | | | | 4/26/2021 |
|-------------|--------------------|---|------|---------------|-------|--------|-----------|
| Item# | Division | Trade/Description | Cost | | \$/SF | | Project % |
| 1 | Div 01 | General Requirements | \$ | 357,066.00 | \$ | 4.15 | 1.62% |
| 2 | Div 02 | Existing Conditions | \$ | 1,548,720.00 | \$ | 18.00 | 7.01% |
| 3 | Div 03 | Concrete | \$ | 1,849,860.00 | \$ | 21.50 | 8.38% |
| 4 | Div 04 | Masonry | \$ | 1,247,580.00 | \$ | 14.50 | 5.65% |
| 5 | Div 05 | Metals | \$ | 1,548,720.00 | \$ | 18.00 | 7.01% |
| 6 | Div 06 | Woods, Plastics and Composites | \$ | 1,062,594.00 | \$ | 12.35 | 4.81% |
| 7 | Div 07 | Thermal and Moisture Protection | \$ | 946,440.00 | \$ | 11.00 | 4.29% |
| 8 | Div 08 | Openings | \$ | 258,120.00 | \$ | 3.00 | 1.17% |
| 9 | Div 09 | Finishes | \$ | 2,237,040.00 | \$ | 26.00 | 10.13% |
| 10 | Div 10 | Specialties | \$ | 503,334.00 | \$ | 5.85 | 2.28% |
| 11 | Div 11 | Equipment | \$ | 43,020.00 | \$ | 0.50 | 0.19% |
| 12 | Div 12 | Furnishings | \$ | 30,114.00 | \$ | 0.35 | 0.14% |
| 13 | Div 13 | Special Construction | \$ | 21,510.00 | \$ | 0.25 | 0.10% |
| 14 | Div 14 | Conveying Equipment | \$ | 1,505,700.00 | \$ | 17.50 | 6.82% |
| 15 | Div 21 | Fire Supression | \$ | 410,581.00 | \$ | 4.77 | 1.86% |
| 16 | Div 22 | Plumbing | \$ | 1,892,880.00 | \$ | 22.00 | 8.57% |
| 17 | Div 23 | Heating, Ventilating and Air-Conditioning | \$ | 2,473,650.00 | \$ | 28.75 | 11.20% |
| 18 | Div 26 | Electrical | \$ | 2,280,060.00 | \$ | 26.50 | 10.33% |
| 19 | Div 27 | Communications | \$ | 32,695.20 | \$ | 0.38 | 0.15% |
| 20 | Div 28 | Electronic Safety and Security | \$ | 344,160.00 | \$ | 4.00 | 1.56% |
| 21 | Div 31 | Earthwork | \$ | 1,161,540.00 | \$ | 13.50 | 5.26% |
| 22 | Div 31 | Exterior Improvements | \$ | 107,550.00 | \$ | 1.25 | 0.49% |
| 23 | Div 33 | Utilities | \$ | 219,402.00 | \$ | 2.55 | 0.99% |
| | | Trade Subtotal - Pre- General Conditions | \$ | 22,082,336.20 | \$ | 256.65 | 100.00% |
| | | Building Permit Fees (1%) | \$ | 220,823.36 | \$ | 2.57 | 1.00% |
| | | General Conditions (5%) | \$ | 1,104,116.81 | \$ | 12.83 | 5.00% |
| | | CM Staff (10%) | \$ | 2,208,233.62 | \$ | 25.67 | 10.00% |
| | | Overhead and Profit (6%) | \$ | 1,324,940.17 | \$ | 15.40 | 6.00% |
| | | Insurance (5%) | \$ | 1,104,116.81 | \$ | 12.83 | 5.00% |
| | | Payment and Performance Bond (3%) | \$ | 662,470.09 | \$ | 7.70 | 3.00% |
| | | Trade Total | \$ | 28,707,037.06 | \$ | 333.65 | |
| | | Connect Construct CM FEE (3.5%) | \$ | 1,004,746.30 | \$ | 11.68 | 3.50% |
| | | Total Cost with out Contingencey | \$ | 29,711,783.36 | \$ | 345.33 | |
| | | Contingency by Ownership (3%) | \$ | 891,353.50 | \$ | 10.36 | 3.00% |





Breakdown

of Project Direct Costs


40-09 21st Street, Long Island City, NY 11101

Urban Yard Interior Renovation

Project Direct Costs

| Trade | Cost | | % of Total Project |
|------------------------------------|------|--------------|--------------------|
| MEPS | \$ | 7,434,026.20 | 33.67% |
| Demo & Excavation | \$ | 2,710,260.00 | 12.27% |
| Specialties & Equipment | \$ | 546,354.00 | 2.47% |
| Concrete & Masonry | \$ | 3,097,440.00 | 14.03% |
| Exterior Improvements | \$ | 107,550.00 | 0.49% |
| Steel (Structural & Misc. Metals) | \$ | 1,548,720.00 | 7.01% |
| Utilities | \$ | 219,402.00 | 0.99% |
| Elevators | \$ | 1,505,700.00 | 6.82% |
| Rough & Finish Carpentry/Millwork | \$ | 1,062,594.00 | 4.81% |
| Finishes | \$ | 2,237,040.00 | 10.13% |
| General Requirements | \$ | 357,066.00 | 1.62% |
| Doors and Hardware | \$ | 258,120.00 | 1.17% |
| Insulation & Waterproofing | \$ | 946,440.00 | 4.29% |
| Furnishings & Special Construction | \$ | 51,624.00 | 0.23% |

Direct Costs Total: \$ 22,082,336.20



Detailed Trade Takeoff (Sprinklers)

| Construct Connect Deta | ailed Trade | Takeoff | | | | | | | | |
|--|------------------|--------------------|----------|--------------------|---------|----------------------|----------|------------|--------------------|--|
| 624 W139th Street, New York, NY 10031 Spri | nkler Systen | n | | | | | | NNE | | New Sprinkler Pipin |
| | natura arreste e | 2012 - 2012 C | | | ÷., | | | | RUCT | New Pendant Heads |
| 40-09 21st Street, Long Urb | an Yard Inte | erior Ren | ova | tion | | | Helpir | ng connect | you to your goals" | New Upright Heads |
| Island City, NY 11101 Tota | al Project SF | : 86,040 | | | | | | | | Existing Piping to Re |
| Description | Quantity | Unit | | Unit Cost | | Total | | / sf | % of Total Cost | Existing Heads to Re |
| Description | Quantity | | | Clift Cost | | Total | 3 | 9 / 31 | 76 OI TOTAI COSt | Existing Heads to be |
| | | Cella | | | | | | | | Fire Hose Valve |
| New Sprinkler Piping | 22.4 | 1000 | \$ | 30.00 | \$ | 672.00 | \$ | 0.01 | 0.16% | |
| Standpipe | | ea | \$ | 30,000.00 | \$ | 60,000.00 | \$ | 0.70 | 14.61% | Floor Control Assemi |
| New Pendant Heads | 3 | ea | \$ | 50.00 | \$ | 150.00 | \$ | 0.00 | 0.04% | |
| | | Ground | | | | | | | | New Cosinhias Dinin |
| New Sprinkler Piping | 1093.5 | - CO.S. | \$ | 30.00 | \$ | 32,805.00 | \$ | 0.38 | 7.99% | New Sprinkler Pipin |
| Standpipe | | ea | \$ | 30,000.00 | \$ | 90,000.00 | \$ | 1.05 | 21.92% | New Pendant Heads |
| New Pendant Heads | | ea | \$ | 50.00 | \$ | 3,300.00 | \$ | 0.04 | 0.80% | New Upright Heads |
| New Upright Heads | 5 | | \$ | 50.00 | \$ | 250.00 | \$ | 0.00 | 0.06% | Existing Piping to Re |
| Existing Piping to Remain | 583.4 | | \$ | * | \$ | | \$ | - | 0.00% | Existing Heads to Re |
| Existing Heads to Remain | 65 | | \$ | | \$ | - | \$ | - | 0.00% | |
| Existing Heads to be Removed | 36 | | \$ | - | \$ | - | \$ | - | 0.00% | Existing Heads to be |
| Single Stage Inline Fire Pump | 1 | | \$ | 12,000.00 | \$ | 12,000.00 | \$ | 0.14 | 2.92% | Fire Hose Valve |
| Water Supply Jockey Pump | 8 | ea | \$ | 3,500.00 | \$ | 3,500.00 | \$ | 0.04 | 0.85% | Floor Control Assemi |
| Remote Control Valve DCDA Backflow Device | | | \$ | 450.00 9,250.00 | \$ | 3,600.00 9,250.00 | \$ | 0.04 | 0.88% | |
| Siamese Connection | 1 | ea ea | 5 | 2,250.00 | \$ | 2,250.00 | \$ | 0.03 | 0.55% | |
| Fire Hose Valve | - | ea | \$ | 450.00 | э \$ | 1,350.00 | Ф \$ | 0.03 | 0.33% | New Sprinkler Pipin |
| Floor Control Assembly Valve | | ea | \$ | 10,000.00 | \$ | 10,000.00 | \$ | 0.02 | 2.44% | New Pendant Heads |
| Dry Valve | | ea | \$ | 450.00 | \$ | 450.00 | \$ | 0.01 | 0.11% | New Upright Heads |
| Diy ture | | 2nd Fl | | 100.00 | Ψ. | 100.00 | 4 | 0.01 | 0.1170 | Existing Piping to Re |
| New Sprinkler Piping | 642.3 | - Second States in | \$ | 30.00 | \$ | 19,269.00 | \$ | 0.22 | 4.69% | |
| New Pendant Heads | | ea | \$ | 50.00 | э \$ | 3,150.00 | э \$ | 0.22 | 0.77% | Existing Heads to Re |
| New Upright Heads | 8 | | .р \$ | 50.00 | \$ | 400.00 | .р \$ | 0.04 | 0.10% | Existing Heads to be |
| Existing Piping to Remain | 621.5 | | \$ | 50.00 | \$ | 400.00 | \$ | 0.00 | 0.10% | Fire Hose Valve |
| Existing Heads to Remain | | ea | \$ | | \$ | | \$ | - | 0.00% | Floor Control Assemi |
| Existing Heads to be Removed | | ea | \$ | | \$ | - | \$ | - | 0.00% | |
| Fire Hose Valve | | ea | \$ | 450.00 | \$ | 1,350.00 | \$ | 0.02 | 0.33% | |
| Floor Control Assembly Valve | | ea | \$ | 10,000.00 | \$ | 10,000.00 | \$ | 0.12 | 2.44% | New Sprinkler Pipin |
| | | 3rd Fl | oor | | | | | | | New Pendant Heads |
| New Sprinkler Piping | 650.3 | Souther Cherry | \$ | 30.00 | \$ | 19,509.00 | \$ | 0.23 | 4.75% | New Upright Heads |
| New Pendant Heads | | ea | \$ | 50.00 | \$ | 3,250.00 | \$ | 0.23 | 0.79% | |
| New Upright Heads | | ea | \$ | 50.00 | \$ | 250.00 | \$ | 0.04 | 0.06% | Fire Hose Valve |
| Existing Piping to Remain | 621.5 | | \$ | - | \$ | - | \$ | - | 0.00% | Floor Control Assemi |
| Existing Heads to Remain | 68 | | \$ | - | \$ | - | \$ | - | 0.00% | 3-Way Manifold |
| Existing Heads to be Removed | | ea | \$ | | \$ | - | \$ | - | 0.00% | |
| Fire Hose Valve | | ea | \$ | 450.00 | \$ | 1,350.00 | \$ | 0.02 | 0.33% | Total Sprinkler Co |
| Floor Control Assembly Valve | 1 | ea | \$ | 10,000.00 | \$ | 10,000.00 | \$ | 0.12 | 2.44% | Total Sprinkler Co |
| | | | | | - | | | | | 1. The second se |

Detailed Toda Takesff

| | | 4tl | n Floor | | | | |
|------------------------------|-------|------|---------|-----------|-----------------|------------|------------|
| New Sprinkler Piping | 521.1 | LF | \$ | 30.00 | \$ 15,633.00 | \$ 0.18 | 3.81% |
| New Pendant Heads | 64 | ea | \$ | 50.00 | \$ 3,200.00 | \$ 0.04 | 0.78% |
| New Upright Heads | 5 | ea | \$ | 50.00 | \$ 250.00 | \$ 0.00 | 0.06% |
| Existing Piping to Remain | 505.3 | LF | \$ | - | \$ - | \$ - | 0.00% |
| Existing Heads to Remain | 68 | ea | \$ | 2 | \$ 9 | \$ - | 0.00% |
| Existing Heads to be Removed | 41 | ea | \$ | - | \$ - | \$ - | 0.00% |
| Fire Hose Valve | 3 | ea | \$ | 450.00 | \$ 1,350.00 | \$ 0.02 | 0.33% |
| Floor Control Assembly Valve | 1 | ea | \$ | 10,000.00 | \$ 10,000.00 | \$ 0.12 | 2.44% |
| | | 5tl | n Floor | | | | |
| New Sprinkler Piping | 515.8 | LF | \$ | 30.00 | \$ 15,474.00 | \$ 0.18 | 3.77% |
| New Pendant Heads | 64 | ea | \$ | 50.00 | \$ 3,200.00 | \$ 0.04 | 0.78% |
| New Upright Heads | 5 | ea | \$ | 50.00 | \$ 250.00 | \$ 0.00 | 0.06% |
| Existing Piping to Remain | 505.6 | LF | \$ | - | \$ - | \$ - | 0.00% |
| Existing Heads to Remain | 68 | ea | \$ | 2 | \$ - | \$ - | 0.00% |
| Existing Heads to be Removed | 41 | ea | \$ | - | \$ - | \$ - | 0.00% |
| Fire Hose Valve | 3 | ea | \$ | 450.00 | \$ 1,350.00 | \$ 0.02 | 0.33% |
| Floor Control Assembly Valve | 1 | ea | \$ | 10,000.00 | \$ 10,000.00 | \$ 0.12 | 2.44% |
| | | 6tl | n Floor | | | | |
| New Sprinkler Piping | 711.9 | LF | \$ | 30.00 | \$ 21,357.00 | \$ 0.25 | 5.20% |
| New Pendant Heads | 63 | ea | \$ | 50.00 | \$ 3,150.00 | \$ 0.04 | 0.77% |
| New Upright Heads | 5 | ea | \$ | 50.00 | \$ 250.00 | \$ 0.00 | 0.06% |
| Existing Piping to Remain | 621.8 | LF | \$ | - | \$ 3 | \$ - | 0.00% |
| Existing Heads to Remain | 68 | ea | \$ | 2 | \$ 2 | \$ - | 0.00% |
| Existing Heads to be Removed | 41 | ea | \$ | | \$ - | \$ - | 0.00% |
| Fire Hose Valve | 3 | ea | \$ | 450.00 | \$ 1,350.00 | \$ 0.02 | 0.33% |
| Floor Control Assembly Valve | 1 | ea | \$ | 10,000.00 | \$ 10,000.00 | \$ 0.12 | 2.44% |
| | | Roof | Bulkhea | ad | | | |
| New Sprinkler Piping | 70.4 | LF | \$ | 30.00 | \$ 2,112.00 | \$ 0.02 | 0.51% |
| New Pendant Heads | 7 | ea | \$ | 50.00 | \$ 350.00 | \$ 0.00 | 0.09% |
| New Upright Heads | 1 | ea | \$ | 50.00 | \$ 50.00 | \$ 0.00 | 0.01% |
| Fire Hose Valve | 3 | ea | \$ | 450.00 | \$ 1,350.00 | \$ 0.02 | 0.33% |
| Floor Control Assembly Valve | 1 | ea | \$ | 10,000.00 | \$ 10,000.00 | \$ 0.12 | 2.44% |
| 3-Way Manifold | 3 | ea | \$ | 600.00 | \$ 1,800.00 | \$ 0.02 | 0.44% |
| | | | | | | | |
| Total Sprinkler Cost | | | | | \$ | | 410,581.00 |

<u>Total:</u>


\$410,581.00

Cost per SF:

\$4.77/sf









Flow of Traffic

Adjacent Roadways


- 21st Street
- 22nd Street
- 40th Ave
- 41st Ave




Jobsite Access and Temp Office Location










Utility Service Entry Points



Urban Yard Constructability Review





For us at Connect Construct, constructability reviews are crucial elements of the preconstruction phase we like to put an emphasis on. This can be critical to ensuring a successful project by identifying and eliminating any potential discrepancies that can become an issue down the road.

A constructability review is a process we use during the bidding and preconstruction phases that allows us to infuse or construction knowledge into the design process. We noticed two discrepancies in the 90% Construction Document Set dated 10/28/20 that we have received thus far and based our overall project proposal on.





RFI Transmittal

Project:

Request for Information # 001

Initiated Date: 3.8.21 Response Required By: 3.22.21

| Subject | Discipline | Co-Author | Reference Information |
|--|------------|--|-----------------------|
| Submitted To: MSA Murdock Solon Architects 508 W 26 th Street Suite 5B New York, NY 10003 | | Submitted By: Connect Constri 624 W 139 th Stri Suite 4D New York, NY 1 | eet |


Information Requested

Please provide more information regarding roof design for construction. The drawings provided are not clear on whether there is a new membrane being installed or if the existing is staying.

If existing stays: Are there any repairs needed? Has there been a history of leaks? Please provide details for roof penetrations and pitch pockets.

If there is new roof: Please provide specifications for desired system. Please provide details for roof penetrations and pitch pockets. ENGINEER/ ARCHITECT RESPONSE

Your immediate response is required to avoid delays in detailing, engineering, fabrication, and installation. Answered by: Date Answered:



1. RFI #001 – Roof Construction Design

It is unclear in the drawings provided whether the roof construction is to be new or if there is an existing membrane to remain. Both options will require further information and input from the design team. If the roof is to remain then it is necessary to know if it needs any repairs which would be contingent on when the existing membrane was installed and the system that was installed. Roofs generally need repaired or replaced every 20 years on average. If there is to be a new roof membrane installed then Connect Construct will need to know the desired manufacturer, R-Value requirements, and warranty requirements. For both options, existing and new, we will need further details for roof penetrations and pitch pockets.




RFI Transmittal

| Project: Urban Yard 40-09 21" Street Long Island City, NY 11101 | Response Required By: 3.22.21 |
|---|--|
| 40-09 21st Street | |
| | |
| Submitted To: | Submitted By: |
| MSA Murdock Solon Architects 508 W 26th Street Suite 5B New York, NY 10003 | Connect Construct 624 VV 139 th Street Suite 4D New York, NY 10031 |
| Subject Discipline | Co-Author Reference Information |
| Bulkhead Exterior Masonry Brick Mas | sonry Architectural Drawings |
| | |
| ENGINEER/ ARCHITECT RESPONSE | |
| | |
| | |
| | |

Answered by:

Date Answered:



1. RFI #002 - Bulkhead Masonry Curtain Wall

There is further information required for the construction of the masonry curtain wall cladding for the new rooftop bulkhead. Clarification is needed on the type of brick (size, pattern, colors, manufacturer, grade) as well as general masonry curtain wall such as brick ties and horizontal reinforcement.




Site Safety

- Nothing is more important than worker safety
- Construction ranks one of the highest in occupational hazard industries
- Connect Construct EMR = 0.79
- EVERYBODY GOES HOME SAFE

CONNECT CONSTRUCT "Helping connect you to your goals"

Typical Construction Floor Safety Mitigation Floor Plan




Safety Risks


- Fall Hazards
- Hot Works
- COVID-19
- Material Hoisting











URBAN YARD PROXIMITY TO FIRE HOUSES

CONNECT CONSTRUCT QUALITY ASSURANCE AND QUALITY CONTROL

Quality Assurance and Quality Control are key components to the successfully delivery of any construction program. Here at Connect Construct we have a robust, integrated program for both.

Quality Assurance comes first to make sure everything to be installed and constructed conforms with the design intent and specifications.

<u>Quality Control</u> is an ongoing process carried out during the construction phases with continuous inspection and verification that items installed, and work carried out continue to remain in conformance.





Quality Assurance:


- Submittals
- Mockups and samples
- Manufacturer Certifications and Warranties

Quality Control:

- Delivery Inspections
- Testing and Inspections
- Daily Reports and Field Inspections







Value Engineering

What is Value Engineering?

Also known as a value analysis, is the process of evaluating documented design to identify potential alternative methods, systems, or materials that will benefit the owner by enhancing the life cycle of the project." – CSI PRM 4.7.7

Value engineering relies heavily on team building, effective communication, and efficient decision making to reach creative solutions. By working together, we are able to arrive at unique approaches to specific design elements to satisfy your project vision and save you money on the project cost.







The term Value Analysis was first coined by General Electric during World War II. Due to the shortage of materials in that period they needed to find substitutes. As they found options that were available, cost less, and performed equally well or better, Value Analysis became a process inherent in their operational approach. Keeping in spirit with this, Connect Construct has maintained an ethos of keeping value analysis/engineering as an inherent element in how we approach a project. <image><text><text><text><text><text><text><text>



Elkay SwirlFlo Bi-Level Fountain Non-Filtered Non-Refrigerated, Freeze Resistant Stainless EDFPBM117FPK

\$4,513 (List price shown in US dollars. Actual selling price may vary.)



**** 0 Reviews

2 questions and 2 answers for this product

WRITE A REVIEW





Elkay ERPBM28K Refrigerated Drin SwirlFlo, 8.0 GPH Water Cooler, AD Non-Filtered, Stainless Steel

ELKAY


Lead Time - 3 to 7 business days (Due surge in orders, lead times may be exte

Our Price: **\$1,899.00**

List Price: \$4,757.00 | Savings: \$2,858.00

SKU: ERPBM28KAvailability: ✓ In Stock

CHOOSE YOUR PRODUCT OPTIONS:



| | CORP | | | | | | | | - |
|-----|------|-----|------|-------|----|------|------|------|---|
| | ۲ | ۲ | ۲ | ۲ | | ۲ | ۲ | ۲ | |
| aų. | 000 | 000 | 1001 | 13281 | FI | 1950 | 1991 | 1620 | |

| AREA MARK | NAME | PAGE |
|-----------|-----------------|------|
| в | ELEVATOR-A | I-12 |
| С | ELEVATOR-B | 1-12 |
| D | STAIRWELL | 1-11 |
| E | TYP. HALLWAY | 1-08 |
| F | PUBLIC RESTROOM | 1-13 |

Value Engineered Results

Cost for Elkay as Specified Option \$27,078.00

Cost for Elkay VE Option \$11,394.00

Total Savings of \$15,683.00

ELKAY SPECIFICATIONS

PRODUCT SPECIFICATIONS


Elkay SwirfFlo® Fountain Bi-Level ADA Non-Filtered, 8 GPH Stainless. Chilling Capacity of 8.0 GPH (gallons per hour) of 50° F drinking water, based on 80° F inlet water and 90° F ambient, per ASHRAE 18 testing. Furnished with Flexi-Guard® Safety bubbler. Mechanical Front Bubbler Button activation. Product shall be Wall Mount (In-Wall Frame/Plate), for Indoor applications, serving 2 station(s). Unit shall be certified to UL 399 and CAN/CSA C22.2 No. 120. Unit shall be lead-free design which is certified to NSF/ANSI 61 & 372 (lead free) and meets Federal and State low-lead requirements.

| Finish: | Stainless Steel |
|---|--|
| Power: | 115V/60Hz |
| Bubbler Style: | Flexi-Guard® Safety |
| Activation by: | Mechanical Front Bubbler Button |
| Mounting Type: | Wall Mount (In-Wall Frame/Plate) |
| Chilling Option*: | 8.0 GPH |
| Rated Watts: | 370 |
| Dimensions (L x W x H): | 38-1/2" x 19" x 40-13/16" |
| Approx. Shipping Weight: | 141 lbs. |
| Installation Location: | Indoor |
| No. of Stations Served: | 2 |
| *Based on 80° F inlet water & drinking water. | 90° F ambient air temp for 50° F chilled |

 Mechanically-Activated bubbler continues to supply water in event of service disruptions.

COOLING SYSTEM

- Compressor: Hermetically-sealed, reciprocating type, single phase. Sealed-in lifetime lubrication.
- Condenser: Fan cooled, copper tube with aluminum fins. Fan motor is permanently lubricated.
- Cooling Unit: Combination tube-tank type. Continuous copper tubing with is fully insulated with EPS foam that meets UL requirements for self-extinguishing material.
- Refrigerant Control: Refrigerant R-134a is controlled by accurately calibrated capillary tube.
- Temperature Control: Easily accessible enclosed adjustable thermostat is factory preset. Requires no adjustment other than for altitude requirements.



AMERICAN PRIDE. A LIFETIME TRADITION. Like your family, the Elkay family has values and traditions that endure. For almost a century, Elkay has been a family-owned and operated company, providing thousands of jobs that support our families and communities.

Included with Product: Fountain, Chiller, Mounting Frame

▼ Ships in multiple boxes. PRODUCT COMPLIANCE

ADA & ICC A117.1

Buy American Act

CAN/CSA C22.2 No. 120

NSF/ANSI 61 & 372 (lead free)

UL 399



Complies with ADA & ICC A117.1 accessibility requirements when installed according to the requirements outlined in these standards. Installation may require additional components and/or construction features to be fully compliant. Consult the local Authority Having Jurisdiction if necessary.

Installation Instructions (PDF) - 1000003097 Installation Instructions (PDF) - 97924C Installation Instructions (PDF) - 97153C

5 Year Limited Warranty on the refrigeration system of the unit. Electrical components and water system are warranted for 12 months from date of installation. Warranty nertains to drinking water


Sustainable Construction

Why is Sustainable Construction Important?

- Construction makes up approx. 6.36% of the American GDP.
- Many smaller industries make up the construction industry
- Rapidly growing population + finite resources on Earth.
- Sustainable construction is not just about the creation of a building that has a low environmental impact; it is a new approach in the building sector that improves the way people live and build.

How does construction affect climate change?

- Poorly designed and constructed building use more energy, increasing the demand on energy production and contributing to global warming.
- Large amounts of natural resources go into producing construction products.
- Concrete: Concrete is the most widely used artificial material in existence. The only thing we consume more than concrete is water. The production of concrete releases massive amounts of carbon dioxide into the atmosphere.



If concrete were a country, it would be the third-highest emitter of carbon dioxide.

Sustainable Measures for Urban Yard

- Recycled concrete
- Dust control measures (Spraying water & dust collectors)
- Waste management services.
- Indoor Air Quality Plan
- Noise control / reduction

MR. TCARTING



Learn More About Recycled Concrete

We are dedicated to providing you with high-quality concrete pumping services with minimal environmental impact.

CONTACT US



Construction Technology

\bigcirc

Construction Technology

Procore

- Track RFI & Submittals
- View all drawings and revisions
- View project specifications
- View and distribute meeting minutes
- View and distribute daily reports
- View and distribute punch lists

PROJECT TEAM

| flate | Blarme | Baranti. | \$Pfice | Moto In |
|---------------------------|--------------------------------------|--------------------------------|----------------|----------------|
| lenharical Engloeer | Gaty Boll (Bell Factorition) | gielgibelexavalian.com | (530) 812 8111 | (530) 221 6551 |
| lainer | Ayer Pain (Zion High School Dismirt) | ayer policitization in edu | (330) 288 9722 | (530) 165 9659 |
| Voject Manager | Jeff Kemper (Jewett Communition) | jeffkgsjewettio.com | (209) 800-0404 | (209) 909-9574 |
| Reperintendent. | Actom Opininer (Spininer Steet) | odam.apinneigspittiersteit.com | 00995-825-1401 | (206) 663-2445 |
| Assistant Superintendent. | Like Wilson (Jennet Modular Systems) | lukewaterarctinodular.com | (2090 825-2768 | (2090 510-7618 |

PROJECT OVERVIEW






Construction Technology


Planswift

- View and markup drawings
- Perform detailed quantity take offs
- Generate comprehensive reports
- Scale drawings
- Overlay drawings to easily view revisions





Construction Technology



Navisworks

- 3D Building Modelling
- Clash detection
- Expedited fabrication
- Solve and identify potential construction issues virtually, saves time and prevents delays

AUTODESK® NAVISWORKS

Construction Technology

Microsoft Project

- Develop and update project schedule
- Develop Critical Path
- Develop and maintain project plan
- Allocation of resources
- Generate logical visual for team members to follow

| P S FIL | E. | -¥ TAS | ち・ ぐ K RES | → → OURCE REPORT PROJECT | | FORMAT | | | W | ELLMONT Tot | tal Slack Upc | lated No | PM Begin 2.r | mpp - Pro | oject Stan | idard | | | |
|----------------------------|-----------|------------|-----------------------------------|----------------------------------|----------------|--|---------------------------|--|------------------|-------------|---------------|-------------|--------------------|-----------|----------------|---------------------------------------|-----------------|-------------|------------------------------|
| Gan Gan Char Viev | tt t ∗ | Paste | Cut Copy Forma Clipboard | t Painter B I U 🖄 - 🛆 - | 0× 25× 50× 75× | 🛛 🗔 💭 🧊 Mark യ 🔅 🍄 Resp Schedule | c on Track 🔹 ect Links | Manually Auto Schedule Schedule | Inspect Tasks | Move Mod | e Task | tinser | ry Milestone It | Informa | ition | Notes Details Add to perties | s o Timeline | | Cle Cle Fill diting |
| | | 0 | Task Mode 🕶 | Task Name | Duration 👻 | Predecessors 🗸 | Start | ▼ Finish ▼ | 14 21 | Jan 15 | Feb ' | | Mar 15 | | Apr 15 5 12 | 19 2 | May '15 | | Jun '15 31 7 |
| | 1 | 15 | - | Notice to Proceed | 0 days | | Mon 1/5/15 | | | : | 1 | | 1 | 1 | | 18 1 | 4 | 1 | |
| | 2 | 1 | - | Project Start | 0 days | 1SS+2 days | Tue 1/6/15 | Tue 1/6/15 | | 40 | | | | | | | | | |
| | 3 | 1 | - | Mobilization | 10 days | | Wed 1/7/15 | and the second sec | | | Mobiliz | ation | | ····· | | | 1 | | |
| | 4 | 1 | - | Mobilize | 10 days | 255 | Wed 1/7/15 | Thu 1/22/15 | 10 | 00% | Mobilize | | | | | | | | |
| | 5 | 5 | - | Construction | 34 days | | Mon 1/26/1 | 5 Tue 3/24/15 | | | | | | | nstructi | on | | | |
| | 6 | | | # Below Grade | 13 days | | Mon 1/26/1 | 5 Mon 2/16/15 | | | | B | elow Grade | | | | | | |
| | 7 | 1 | - | Grade Site | 8 days | 4 | Mon 1/26/1 | 5 Thu 2/5/15 | | 100 | % | rade Si | te | | | | | | |
| | 8 | 1 | - | Set Foundations | 9 days | 4 | Mon 1/26/1 | 5 Mon 2/9/15 | | 100 | % | Set Fo | undations | | | | | | |
| - | 9 | ~ | - | Install Conduit | 3 days | 7 | Mon 2/9/15 | Wed 2/11/15 | | | 100% | Insta | II Conduit | | | | | | |
| | 10 | G | - | Dig Cable Trench | 4 days | 8 | Tue 2/10/15 | Mon 2/16/15 | | | 75% | 📥 Di | g Cable Trei | nch | | | | | |
| | 11 | 5 | - | Above Grade | 23 days | | Thu 2/12/15 | Tue 3/24/15 | | | | | | Ab | ove Gra | de | | | |
| | 12 | . 4 | - | Erect Steel Structures | 8 days | 9 | Thu 2/12/15 | Wed 2/25/15 | | | 13% | - | Erect Stee | Structu | ires | | | | |
| | 13 | 1 4 | - | Install Equipment | 6 days | 10 | Tue 2/17/15 | Wed 2/25/15 | | | 4 | 0% | Install Equ | uipment | | | | | |
| | 14 | - 6 | - | Install Grounding | 2 days | 12 | Thu 2/26/15 | Mon 3/2/15 | | | | 0% | install | Groundi | ng | | | | |
| | 15 | ٩. | 100, C | Install Bus and Jumpers | 8 days | 12 | Thu 2/26/15 | Wed 3/11/15 | | | | 0% | Ins | tall Bus | and Ju | mpers | • | | |
| | 16 | . | - | Lay Control Cable | 12 days | 13FS+30 hrs | Wed 3/4/15 | Tue 3/24/15 | 230303030303030 | | | 13030013030 | 0% | Lay | Control | I Cabl | e | | |
| RT | 17 | 5 | - | # Fence | 7 days | | Mon 2/9/15 | Wed 2/18/15 | | | | - 1 | ence | | | | | | |
| CHART | 18 | - 9 | - | Install Fence | 7 days | 7 | Mon 2/9/15 | Wed 2/18/15 | | | 57% | In | stall Fence | | | | | | |
| | 19 | 5 | | Site Restoration | 26 days | | Tue 2/17/15 | Wed 4/1/15 | | | | - | | | Site Re | estora | tion | | |
| GANTI | 20 | - | - | Remove Equipment | 5 days | 16 | Wed 3/25/1 | 5 Wed 4/1/15 | | | | | |)% 🏣 | Remove | e Equi | ipment | | |
| Ĩ., | 21 | 1.00 | - | Lay Stoning | 2 days | 10 | Tue 2/17/15 | Wed 2/18/15 | | | (| 0% L | ay Stoning | | | | | | |
| | 22 | . Q | - | Lay Roadway | 4 days | 10 | Tue 2/17/15 | Mon 2/23/15 | | | (| 0% 🎽 | Lay Roadw | ay | | | | | |
| | 23 | 5 | 100 g | Project Closeout | 10 days | | Thu 4/2/15 | Mon 4/20/15 | | | | | | | | 1000 | oject Clo | 2010/02/201 | |
| | 24 | . 4 | - | Substaintial Completion | 10 days | 14,15,18,20,21, | Thu 4/2/15 | Mon 4/20/15 | | | | | | 0% | <u> </u> | Sul | ostaintial | Comple | tion |
| | 25 | | | Project Complete | 1 day | 24FF | Mon 4/20/1 | 5 Mon 4/20/15 | | | | | | | | 4 | | | |

Project



CONNECT CONNECT CONSTRUCT "Helping connect you to your goals"